


SE NE SE SW

WATER WELL RECORD

Form WWC-5

KSA 82a-1212

1 LOCATION OF WATER WELL: County: <u>Seelye</u>		Fraction <u>1/4</u> <u>1/4</u> <u>8th</u> <u>1/4</u>	Section Number <u>16</u>	Township Number T <u>26</u> S	Range Number R <u>2</u> E <u>(W)</u>
Distance and direction from nearest town or city street address of well if located within city: <u>119 Centennial Ct Colwich KS</u>					
2 WATER WELL OWNER: RR#, St. Address, Box #: City, State, ZIP Code:		Sueffentrop Const. <u>632 Seville</u> <u>Wichita 67209</u>			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: <u>64</u> ft. ELEVATION: Depth(s) Groundwater Encountered 1. <u>26</u> ft. 2. <u>26</u> ft. 3. <u>12-14-81</u> ft. WELL'S STATIC WATER LEVEL <u>26</u> ft. below land surface measured on mo/day/yr Pump test data: Well water was <u>26</u> ft. after <u>20</u> hours pumping <u>20</u> gpm Est. Yield <u>50</u> gpm: Well water was <u>26</u> ft. after <u>20</u> hours pumping <u>20</u> gpm Bore Hole Diameter <u>11</u> in. to <u>64</u> ft. and <u>64</u> in. to <u>64</u> ft. WELL WATER TO BE USED AS: ☒ Domestic ☐ 3 Feedlot ☐ 6 Oil field water supply ☐ 9 Dewatering ☐ 12 Other (Specify below) ☐ 2 Irrigation ☐ 4 Industrial ☐ 7 Lawn and garden only ☐ 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes <u>X</u> No <u>X</u> ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes <u>X</u> No <u>X</u>			
5 TYPE OF BLANK CASING USED: 1 Steel ☒ 3 RMP (SR) 2 PVC ☒ 4 ABS Blank casing diameter <u>5</u> in. to <u>55</u> ft. Dia <u>55</u> in. to <u>55</u> ft. Dia <u>55</u> in. to <u>55</u> ft. Dia <u>55</u> in. to <u>55</u> ft. Casing height above land surface <u>12</u> in., weight <u>1.59</u> lbs./ft. Wall thickness or gauge No. <u>50R-26</u>		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued <u>X</u> Clamped <u>X</u> 6 Asbestos-Cement 9 Other (specify below) Welded <u>X</u> 7 Fiberglass Threaded <u>X</u>			
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass ☒ 8 RMP (SR) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 10 Asbestos-cement 11 Other (specify) 12 None used (open hole)		SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot ☒ 3 Mill slot 2 Louvered shutter 4 Key punched 5 Gauzed wrapped 6 Wire wrapped 7 Torch cut 8 Saw cut 9 Drilled holes 10 Other (specify) 11 None (open hole)			
SCREEN-PERFORATED INTERVALS: From <u>55</u> ft. to <u>64</u> ft. From <u>55</u> ft. to <u>64</u> ft. From <u>55</u> ft. to <u>64</u> ft. From <u>55</u> ft. to <u>64</u> ft. GRAVEL PACK INTERVALS: From <u>16</u> ft. to <u>64</u> ft. From <u>16</u> ft. to <u>64</u> ft. From <u>16</u> ft. to <u>64</u> ft. From <u>16</u> ft. to <u>64</u> ft.		6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ 3 Bentonite 4 Other Grout Intervals: From <u>6</u> ft. to <u>16</u> ft. From <u>6</u> ft. to <u>16</u> ft. From <u>6</u> ft. to <u>16</u> ft. From <u>6</u> ft. to <u>16</u> ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines ☒ 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage Direction from well? <u>West</u> How many feet? <u>25</u>			
FROM TO LITHOLOGIC LOG		FROM TO LITHOLOGIC LOG			
0 2 Top soil					
2 21 Red clay					
21 31 fine sand					
31 34 Red clay					
34 50 med sand					
50 51 Red clay					
51 64 gravel					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>3-18-81</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>318</u> This Water Well Record was completed on (mo/day/yr) <u>1-7-82</u> under the business name of <u>Wenger Drilling</u> by (signature) <u>Wenger</u>					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					