


LOCATION OF WATER WELL: Fraction NE 1/4 NE 1/4 SE 1/4 Section Number 18 Township Number T 26 S Range Number R 2 E
 County: Edgworth
 Distance and direction from nearest town or city street address of well if located within city?
1/2 mi. Colwich KS

WATER WELL OWNER: John Schwartz
 RR#, St. Address, Box # :
 City, State, ZIP Code: Colwich KS 67030

Board of Agriculture, Division of Water Resources

Application Number:

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: 50 ft. ELEVATION:Depth(s) Groundwater Encountered 1. 22 ft. 2. ft. 3. ft.WELL'S STATIC WATER LEVEL 22 ft. below land surface measured on mo/day/yr 6-20-81Pump test data: Well water was 23 ft. after 12 hours pumping 30 gpmEst. Yield 40 gpm: Well water was ft. after hours pumping gpmBore Hole Diameter 11 in. to 50 ft., and in. to ft.

WELL WATER TO BE USED AS:

☒ 1 Domestic ☐ 3 Feedlot ☐ 6 Oil field water supply ☐ 9 Dewatering ☐ 12 Other (Specify below)

☐ 2 Irrigation ☐ 4 Industrial ☐ 7 Lawn and garden only ☐ 10 Observation well

 Was a chemical/bacteriological sample submitted to Department? Yes ☒ No ☒ If yes, mo/day/yr sample was submitted
 Water Well Disinfected? Yes ☒ No ☒

TYPE OF BLANK CASING USED:

☐ 1 Steel ☒ 3 RMP (SR)
☐ 2 PVC ☐ 4 ABS

☐ 5 Wrought iron ☐ 8 Concrete tile
☐ 6 Asbestos-Cement ☐ 9 Other (specify below)
☐ 7 Fiberglass
CASING JOINTS: Glued ☒ Clamped

Welded

Threaded

 Blank casing diameter 5 in. to 40 ft. Dia. in. to ft. Dia. in. to ft.
 Casing height above land surface 12 in., weight 1.59 lbs./ft. Wall thickness or gauge No. SPE-26

TYPE OF SCREEN OR PERFORATION MATERIAL:

☐ 1 Steel ☐ 3 Stainless steel
☐ 2 Brass ☐ 4 Galvanized steel

☐ 5 Fiberglass
☐ 6 Concrete tile
☒ 7 PVC☐ 10 Asbestos-cement☐ 11 Other (specify)☐ 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

☐ 1 Continuous slot ☒ 3 Mill slot
☐ 2 Louvered shutter ☐ 4 Key punched
☐ 5 Gauzed wrapped☐ 8 Saw cut☐ 11 None (open hole)☐ 6 Wire wrapped☐ 9 Drilled holes☐ 7 Torch cut☐ 10 Other (specify)
 SCREEN-PERFORATED INTERVALS: From 40 ft. to 50 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

 GRAVEL PACK INTERVALS: From 15 ft. to 50 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

GROUT MATERIAL:

☐ 1 Neat cement☒ 2 Cement grout☐ 3 Bentonite☐ 4 OtherGrout Intervals: From 5 ft. to 15 ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination:

☐ 1 Septic tank☐ 4 Lateral lines☐ 7 Pit privy☐ 10 Livestock pens☐ 14 Abandoned water well☒ 2 Sewer lines☐ 5 Cess pool☐ 8 Sewage lagoon☐ 11 Fuel storage☐ 15 Oil well/Gas well☐ 3 Watertight sewer lines☐ 6 Seepage pit☐ 9 Feedyard☐ 12 Fertilizer storage☐ 16 Other (specify below)☐ 13 Insecticide storage

Direction from well?

WestHow many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Top soil			
2	18	Red clay			
18	32	fine sand			
32	33	Red clay			
33	50	med gravel			

 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6-20-81 and this record is true to the best of my knowledge and belief. Kansas

 Water Well Contractor's License No. 318 This Water Well Record was completed on (mo/day/yr) 6-26-81
 under the business name of Weninger Pully by (signature) James Weninger

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY

T

R

EW

SEC.

18

NE

NE

SE