


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

☒ Location of well:	County Sedwick	Fraction C SW 1/4 1/4 1/4 1/4	Section number 35	Township number T 26	Range number S R 24 E/W
☒ Distance and direction from nearest town or city: 2 1/2 - 3.50. of Maize, Ks. Street address of well location if in city:			3. Owner of well: Cleo Lagaly R.R. or street: City, state, zip code: Colwich, Kans. 67030		
4. Locate with "X" in section below: N 1 Mile W  E S 1 Mile			Sketch map: Center of Quarter		
5. Type and color of material			From	To	6. Bore hole dia. 28 in. Completion date Dec 9-77 Well depth 130 ft.
Top - Clay			0'	15'	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
BROWN Sand			15'	20'	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
COURSE GRAVEL			20'	35'	9. Casing: Material Steel Height: (Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 130 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 Ga.
COURSE Sand - COURSE GRAVEL			35'	40'	10. Screen: Manufacturer's name W. A. BROWN ENTERPRISES Type ST. FREE-FLOW Dia. 16" Slot/gauze 1/4 Length 70' Set between 60 ft. and 130 ft. ☐ ft. and ☐ ft. Gravel pack? ☒ Size range of material 1/8 - 3/8
White clay			40'	42'	11. Static water level: ☐ mo./day/yr. 20 ft. below land surface Date Dec 9-77
COURSE GRAVEL			42'	80'	12. Pumping level below land surfaces: 36 ft. after 4 hrs. pumping 900 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1600 g.p.m.
BROWN Sand			80'	95'	13. Water sample submitted: ☐ Yes ☒ No Date ☐ mo./day/yr.
COURSE Sand - FINE GRAVEL			95'	130'	14. Well head completion: ☐ Pitless adapter 12 inches above grade
1/4" steel plate welded to bottom of casing					15. Well grouted? ☐ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 3 ft. to 14 ft.
					16. Nearest source of possible contamination: ft. 2000 Direction NORTH Type FARM STRAD Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: ☐ Not installed Manufacturer's name AURORA-Vertiline Model number ☐ HP ☐ Volts Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Wells Drilling Co. 112 Business name License No. Address 1030 Hwy 54 East Signed Elyse Bayer Date Dec 9-77 Authorized representative
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks:				

Forward the white, blue and pink copies to the Department of Health and Environment

Kingman, Kans.

Form WWC-5