


1 LOCATION OF WATER WELL: County: <u>Sedwick</u>		Fraction <u>NW</u> $\frac{1}{4}$ <u>SE</u> $\frac{1}{4}$ <u>SW</u> $\frac{1}{4}$		Section Number <u>4</u>		Township Number <u>T 26S</u> <u>S</u>		Range Number <u>R 2</u> <u>E/W</u>																																																												
Distance and direction from nearest town or city street address of well if located within city? <u>2 Miles North of Colwich, Kns.</u>																																																																				
2 WATER WELL OWNER: <u>B.W. Spexarth</u> RR#, St. Address, Box # : <u>145 So. 6th ST.</u> City, State, ZIP Code : <u>Colwich, Kansas 67030</u>						Board of Agriculture, Division of Water Resources Application Number: <u>20,648</u>																																																														
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 			4 DEPTH OF COMPLETED WELL: <u>104'</u> ft. ELEVATION: ft. Depth(s) Groundwater Encountered <u>1</u> <u>29'</u> ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL <u>28'</u> ft. below land surface measured on mo/day/yr Pump test data: Well water was <u>NA</u> ft. after hours pumping gpm Est. Yield gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter <u>28"</u> in. to <u>104'</u> ft. and in. to ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) <u>XX2</u> Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes <u>X</u> No																																																																	
5 TYPE OF BLANK CASING USED: 1 Steel <u>XX2</u> PVC 2 RMP (SR) 4 ABS 5 Wrought iron 6 Asbestos-Cement 7 Fiberglass 8 Concrete tile 9 Other (specify below) Blank casing diameter <u>16"</u> in. to <u>64'</u> ft. Dia in. to ft. Dia in. to ft. Casing height above land surface <u>14"</u> in. weight <u>Sch 40</u> lbs./ft. Wall thickness or gauge No. <u>050</u> TYPE OF SCREEN OR PERFORATION MATERIAL: <u>X</u> 7 PVC 10 Asbestos-cement 1 Steel 2 Brass 3 Stainless steel 4 Galvanized steel 5 Fiberglass 6 Concrete tile 8 RMP (SR) 9 ABS 11 Other (specify) 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 5 Gauzed wrapped 6 Wire wrapped 7 Torch cut 8 Saw cut 9 Drilled holes 11 None (open hole) 1 Continuous slot <u>XX3</u> Mill slot 2 Louvered shutter 4 Key punched 10 Other (specify) SCREEN-PERFORATED INTERVALS: From <u>64'</u> ft. to <u>104'</u> ft. From ft. to ft. From ft. to ft. From ft. to ft. GRAVEL PACK INTERVALS: From <u>104'</u> ft. to <u>22'</u> ft. From ft. to ft. From ft. to ft. From ft. to ft.																																																																				
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout <u>XX3</u> Bentonite 4 Other <u>Top 4' - Cement</u> Grout intervals: From <u>22'</u> ft. to <u>4'</u> ft. From <u>4'</u> ft. to <u>0'</u> ft. From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 2 Sewer lines 3 Watertight sewer lines 4 Lateral lines 5 Cess pool 6 Seepage pit 7 Pit privy 8 Sewage lagoon 9 Feedyard 10 Livestock pens 11 Fuel storage 12 Fertilizer storage 13 Insecticide storage <u>XX14</u> Abandoned water well 15 Oil well/Gas well 16 Other (specify below) Direction from well? <u>North</u> How many feet? <u>20'</u>																																																																				
<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>PLUGGING INTERVALS</th></tr></thead><tbody><tr><td>0'</td><td>12'</td><td>Top soil</td><td></td><td></td><td rowspan="8" style="text-align: center; vertical-align: middle;">Check Plugging Report</td></tr><tr><td>12'</td><td>22'</td><td>Clay.</td><td></td><td></td></tr><tr><td>22'</td><td>29'</td><td>Course sand & Fine Gravel.</td><td></td><td></td></tr><tr><td>29'</td><td>41'</td><td>Clay.</td><td></td><td></td></tr><tr><td>41'</td><td>53'</td><td>Course sand & fine Gravel.</td><td></td><td></td></tr><tr><td>53'</td><td>55'</td><td>Clay.</td><td></td><td></td></tr><tr><td>55'</td><td>69'</td><td>Course sand & Fine Gravel.</td><td></td><td></td></tr><tr><td>69'</td><td>71'</td><td>Clay.</td><td></td><td></td></tr><tr><td>71'</td><td>104'</td><td>Course sand & Fine Gravel.</td><td></td><td></td><td></td></tr><tr><td></td><td></td><td>Red Bed.</td><td></td><td></td><td></td></tr></tbody></table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0'	12'	Top soil			Check Plugging Report	12'	22'	Clay.			22'	29'	Course sand & Fine Gravel.			29'	41'	Clay.			41'	53'	Course sand & fine Gravel.			53'	55'	Clay.			55'	69'	Course sand & Fine Gravel.			69'	71'	Clay.			71'	104'	Course sand & Fine Gravel.						Red Bed.			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																															
0'	12'	Top soil			Check Plugging Report																																																															
12'	22'	Clay.																																																																		
22'	29'	Course sand & Fine Gravel.																																																																		
29'	41'	Clay.																																																																		
41'	53'	Course sand & fine Gravel.																																																																		
53'	55'	Clay.																																																																		
55'	69'	Course sand & Fine Gravel.																																																																		
69'	71'	Clay.																																																																		
71'	104'	Course sand & Fine Gravel.																																																																		
		Red Bed.																																																																		
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) <u>reconstructed</u> , or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>July 23 - 1994</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>112</u> This Water Well Record was completed on (mo/day/yr) <u>AUG 18 1994</u> under the business name of <u>Wells Drilling Co.</u> by (signature) <u>Dal Wells</u>																																																																				
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.																																																																				