


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Edwards	Fraction se 1/4 se 1/4 nw 1/4	Section number 1	Township number T 26 S R 20	Range number X/W
2. Distance and direction from nearest town or city: 6 1/2 s-2 1/2 w of Kinsley, Ks. Street address of well location if in city:			3. Owner of well: Midwest Land & Cattle R.R. or street: Box 64 City, state, zip code: Kinsley, Ks. 67547		
4. Locate with "X" in section below: 			Sketch map:		
5. Type and color of material			Fram	To	6. Bore hole dia. 29 in. Completion date 1-29-75 Well depth 52 ft.
Sandy top soil			0	8	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Brown clay			8	16	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Sand and gravel clean coarse loose			16	42	9. Casing: Material steel Weight: Above or below ☒ Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 52 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7
Sand and gravel little clay			42	50	10. Screen: Manufacturer's name Johnson Type steel Dia. 16 Slot/gauze .060 Length 20 Set between 32 ft. and 52 ft. ft. and ☐ ft.
Brown clay			50	56	11. Static water level: ☐ ma./day/yr. 18 1/2 ft. below land surface Date 6-24-74
Blue clay			56	77	12. Pumping level below land surfaces: 35 ft. after 1 hrs. pumping 500 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 600 g.p.m.
Brown clay			77	85	13. Water sample submitted: ☐ ma./day/yr. ☒ Yes ☐ No Date 6-24-74
					14. Well head completion: ☐ Pitless adapter ☐ Inches above grade
					15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
					16. Nearest source of possible contamination: ft. 3/4 mile on sw Type cerrall Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: ☐ Not installed Manufacturer's name Fairbanks-Morse Model number 5-10ma HP 60 Volts ☐ Length of drop pipe 40 ft. capacity 600 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation: 2230 Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley	19. Remarks: 22329		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Osencrantz-Bemis 134 Business name Great Bend, Ks. 67530 Address S. Kilgore Signed S. Kilgore Authorized representative Date 6-24-74		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5