

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 024 EDWARDS NE 1/4 NE 1/4 NW 1/4 6 T 26 S R 20 W

Distance and direction from nearest town or city street address of well if located within city?
 4 S. OF OFFERLE, KS

2 WATER WELL OWNER: STEVE WETZEL 290

RR#, St. Address, Box #: RR. 1 BOX 32

Board of Agriculture, Division of Water Resources

City, State, ZIP code : OFFERLE, KS 67563-

Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	2	3	4
W	NW	NE	E
SW	SE		

4 DEPTH OF COMPLETED WELL 50 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 16 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 16 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 90 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 5 in. to 30 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 30 ft. to 50 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 50 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 4 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 01 SEPTIC TANK

Direction from well? SE

How many feet? 60

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	BROWN CLAY			
2	16	TAN CLAY			
16	21	05 SAND AND 17 GRAVEL			
21	31	GREY CLAY			
31	37	05 SAND AND 17 GRAVEL			
37	40	TAN CLAY			
40	47	05 SAND AND 17 GRAVEL			
47	49	TAN CLAY			
49	50	GREY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/14/94 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 224

This Water Well Record was completed on (mo/day/yr) 12/17/94

under the business name of CARL HAYSE WATER WELL SVC

by (signature)

Carl Hayse