

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SE 1/4 SE 1/4 NE 1/4 21 T 26 S R 21 E

Distance and direction from nearest town or city street address of well if located within city?
 FROM WINDHORST - 1/2 SOUTH, 1 EAST AND 1/2 SOUTH

2 WATER WELL OWNER: WEISS, EVERT
 RR#, St. Address, Box #: Board of Agriculture, Division of Water Resources
 City, State, ZIP code: OPFERLE, KS 67563- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 105 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 46 ft. below land surface measured on no/day/yr 06/13/94
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 18 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 8 in. to 105 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOED
 Blank casing diameter 5 in. to 105 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 60 ft. to 100 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 40 ft. to 105 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 5 ft. to 40 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? WEST How many feet? 15

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL FINE SAND			
20	30	SANDY CLAY			
30	72	BROWN CLAY			
72	80	GRAY CLAY			
80	90	GRAY SHALE SANDSTONE			
90	105	SANDSTONE CLAY			
105	120	GRAY SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 06/15/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 06/30/94 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Justin Cook*