

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

SPEARVILLE

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

ATSK

1. Location of well: County Ford		Fraction nw 1/4 nw 1/4 ne 1/4		Section number 11		Township number T 26 S R 23 E/W		Range number		
2. Distance and direction from nearest town or city: 1 S. 1 1/2 W. 1 S. 2 W of Spearville, Kans					3. Owner of well: Richard Imel Jr.					
Street address of well location if in city:					City, state, zip code: Spearville, Kansas 67976					
4. Locate with "X" in section below:			Sketch map:			6. Bore hole dia. 8.75 in. Well depth 380 ft. Completion date 5-10-76				
						7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary				
8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other						9. Casing: Material pipe Height: Above or below <input type="checkbox"/> Thru <input type="checkbox"/> Surface 12 in. Threaded <input type="checkbox"/> Welded GI RMP <input checked="" type="checkbox"/> Weight 560 lbs./ft. Dia. 5 in. to 380 ft. depth Wall Thickness: inches or Dia. 0.250 in. to 0.250 ft. depth gage No. 0.250				
5. Type and color of material:					From		To		10. Screen: Manufacturer's name Jess and Lowell	
Surface					0		3		Type RMP Dia. 5 in	
Brown clay					3		8		Slot/gauze 1/16 Length 30	
light brown clay					8		17		Set between 350 ft. and 380 ft. Gravel pack? <input checked="" type="checkbox"/> yes Size range of material 1/4 1/8	
Yellow clay with crusty rock layers					17		34		11. Static water level: 390 ft. below land surface Date 5-9-76 mo./day/yr.	
Dark blue shale couple rock layers					34		66		12. Pumping level below land surfaces: 310 ft. after 1 hrs. pumping 30 g.p.m.	
Light gray shale					66		95		Estimated maximum yield 20 g.p.m.	
Gray shale with 25-30% red clay mixed					95		110		13. Water sample submitted: no mo./day/yr.	
Light gray shale					110		138		14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter 12 inches above grade	
Light gray sandstone with 40-45% gray shale					138		143		15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From 4 ft. to 14 ft.	
Gray shale with 30-35% red clay mixed					143		168		16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? <input checked="" type="checkbox"/> X Yes <input type="checkbox"/> No	
Gray shale					168		178		17. Pump: <input type="checkbox"/> Not installed	
Gray shale with 35% sandstone					178		184		Manufacturer's name Reda Model number 19d10p201 HP 2 Volts 220	
Gray shale with 20-25% red clay mixed					184		275		Length of drop pipe 336 ft. capacity 30 g.p.m.	
Gray shale					275		338		Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
A-1 brown sandstone					338		385			
(Use a second sheet if needed)										
18. Elevation:		19. Remarks:								
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		Block 17' TOPO CRATEREENS WELL 2443								
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Hodge Drilling Co. License No. 302 Business name K.R.#1 Dodge City, Ks 67801 Address Willie Hodge Jr. Date 5-12-76 Signed Willie Hodge Jr. Authorized representative										

26 230
 R W
 Sec 11
 1/4 1/4 1/4 1/4
 SPEARVILLE

17
2426