

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

F. DODD

Kansas Department of Health and Environment
Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

ATEB

1. Location of well: County **Ford** Fraction **NW 1/4 NW 1/4 NE 1/4** Section number **31** Township number **T 26** Range number **S R 23** EW

2. Distance and direction from nearest town or city: **2 S, 1/4 E, of Wright**
Street address of well location if in city:
3. Owner of well: **Greg Lix**
R.R. or street:
City, state, zip code: **Wright, Ks. 67882**

4. Locate with "X" in section below: Sketch map:

6. Bore hole dia. **8** in. Completion date **11-27-79**
Well depth **148** ft.
7. Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary
8. Use: Domestic Public supply Industry
 Irrigation Air conditioning Stock
 Lawn Oil field water Other
9. Casing: Material **Plastic** Height: **Above** or below
Threaded Welded Surface **12** in.
RMP PVC Weight **2** lbs./ft.
Dia. **5** in. to **120** ft. depth; Wall Thickness: inches or
Dia. in. to ft. depth; gage No. **.250**

5. Type and color of material	From	To
Topsoil	0	3
Clay yellow	3	43
Sand	43	44
Lime stone	44	45
Clay yellow	45	51
Lime stone	51	56
Clay yellow	56	60
Clay white	60	70
Sand fine streaks	70	90
Sand fine	90	105
Sand fine	105	130
Sandy clay coarse sand	130	135
Sand	135	137
Clay blue	(137)	145

10. Screen: Manufacturer's name **Jess-Loell**
Type **RMP** Dia. **5 in**
 Slot gauze **(1/16)** Length **20 ft**
Set between **120** ft. and **140** ft.
Gravel pack Size range of material **1/4-1/8** in.
11. Static water level: **51 1/2** ft. below land surface Date **11-23-79** mo./day/yr.
12. Pumping level below land surfaces:
60 ft. after **1** hrs. pumping **15** g.p.m.
 ft. after hrs. pumping g.p.m.
Estimated maximum yield **30** g.p.m.
13. Water sample submitted: Yes No Date _____ mo./day/yr.
14. Well head completion: Pitless adapter **12** inches above grade
15. Well grouted? **yes**
With: Neat cement Bentonite Concrete
Depth: From **3** ft. to **18** ft.
16. Nearest source of possible contamination:
ft. **2000** Direction **N** Type **Well**
Well disinfected upon completion? Yes No
17. Pump: Not installed
Manufacturer's name **Goulds**
Model number **0ej7412HP 3/4** Volts **220**
Length of drop pipe **105** ft. capacity **10** g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

18. Elevation: **140**
19. Remarks: **TOPG 2483**
137'
51.5'
85.5' sat H.L.

20. Water well contractor's certification:
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.
Knoefler Bros. Drilling
Business name **Jetmore, Ks** License No. **130**
Address **Jetmore, Ks**
Signed **Dale Knoefler** Date **12-8-79**
Authorized representative

236
233
230
231
MIN WANE
1/4 1/4 1/4
Sec

137
2346