

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction NW 1/4 NW 1/4 NW 1/4 Section Number 21 Township Number T 26 S Range Number R 24 W
 COUNTY: POED

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY - 50 BYPASS & 14TH ST. JCT 4 E ON 50 BYPASS

2 WATER WELL OWNER: HUMPHREY, VERL
 RR#, St. Address, Box #: 2321 6TH AVE.
 City, State, ZIP code: DODGE CITY, KS 67801- Board of Agriculture, Division of Water Resources
 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

X			
NW	NE		
SW	SE		

4 DEPTH OF COMPLETED WELL 184 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 93 ft. below land surface measured on 05/24/96
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 50 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm

5 Core Hole Diameter 10 in. to 184 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 184 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 130 ft. to 170 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 184 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 5 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well: How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	40	CLAY CALACHIE			
40	60	CALACHIE ROCK LAYERS			
60	100	FINE SAND CLAY CALACHIE			
100	120	CLAY SAND ROCK LAYERS			
120	140	CLAY SAND ROCK			
140	160	FINE - MED SAND			
160	175	MED-COARSE SAND VERY LOOSE			
175	190	CLAY GRAY CLAY RED BED			
190	200	BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 05/25/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/year) 06/18/96 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*