

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

CAC

1. Location of well:		County Ford	Fraction SW 1/4 NE 1/4 SW 1/4	Section number 20	Township number T 26 S R 24	Range number 24	(EW)
2. Distance and direction from nearest town or city: 1 N & 2 E from Dodge City, Kansas Street address of well location if in city:				3. Owner of well: Ford County Sanitary Landfill R.R. or street: Board of County Commissioners Ford County Court House City, state, zip code: Dodge City, Kansas			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>28</u> in. Completion date <u>5-20-76</u> Well depth <u>227</u> ft.			
		<p>1476' N & 1690' E of the SW corner of SW 1/4, Sec. 20, T26S, R24W, Ford County, Kansas</p>		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary			
5. Type and color of material				From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input checked="" type="checkbox"/> Other	
Top soil				0	3	9. Casing: Material <u>STL</u> Height: <u>Above or below</u> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>36</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>45</u> lbs./ft.	
Tan clay				3	61	Dia. <u>12</u> in. to <u>197</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>330</u>	
Tan clay and caliche				61	112	10. Screen: Manufacturer's name <u>Cook</u> Type <u>WW</u> Dia. <u>12"</u> Slot/gauze <u>1/8"</u> Length <u>30'</u> Set between <u>197</u> ft. and <u>227</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <u>yes</u> Size range of material <u>3.4mm</u>	
Tan and brown clay some sand lenses				112	198	11. Static water level: <u> </u> mo./day/yr. <u>129</u> ft. below land surface Date <u>8-12-75</u>	
Fine to coarse sand with fine to Med. gravel				198	227	12. Pumping level below land surfaces: <u>193</u> ft. after <u>1</u> hrs. pumping <u>490</u> g.p.m. <u>115</u> ft. after <u>1</u> hrs. pumping <u>620</u> g.p.m. Estimated maximum yield <u>650</u> g.p.m.	
Yellow clay and black shale				227	260	13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>	
Brock 227' 129 98' sat thick						14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade	
120						15. Well grouted? <u>yes</u> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>20</u> ft.	
						16. Nearest source of possible contamination: <u>unk</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
						17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Layne & Bowler</u> Model number <u>10KH</u> HP <u>40</u> Volts <u> </u> Length of drop pipe <u>220</u> ft. capacity <u>500</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)							
18. Elevation:		19. Remarks:					
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		<p><u>2565</u> <u>227</u> <u>2338</u></p> <p><u>TOPE</u></p>					
		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Layne-Western Co.</u> <u>150</u> Business name License No. Address <u>Garden City, Kansas</u> Signed <u>R. H. H. H.</u> Date <u>5-26-76</u> Authorized representative					

WR16HT

24
 27
 20
 1/4
 1/4
 1/4
 1/4
 SUNNIESW