

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number  
 COUNTY: 029 FORD | NE 1/4 NW 1/4 NE 1/4 | 31 | T 26 S | R 24 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 1/2 MILE EAST OF DODGE CITY, KANSAS

2 WATER WELL OWNER: FARMLAND INDUSTRIES INC (Hy Plains Beef)  
 RR#, St. Address, Box #: P.O. BOX 67 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: CRETE, NE 68333- Application Number: 32,617

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 173 | ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 56 ft. below land surface measured on mo/day/yr 01/21/93  
 Pump test data: Well water was 68 ft. after 6 hours pumping 760 gpm  
 Estimated Yield 0 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 36 in. to 173 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: ~~DOMESTIC~~ INDUSTRIAL 04  
 Was a chemical/bacteriological sample submitted to department? Yes;  
 If yes, mo/day/yr sample was submitted 01/25/93 Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 173 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 24 in., weight 63 lbs/ft. Wall thickness or gauge No. .365  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 118 ft. to 168 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 106 ft. to 173 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 01 NEAT CEMENT  
 Grout intervals: From 0 ft. to 106 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? NORTHWEST How many feet? 280

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	01 CLAY			
2	31	04 SANDY CLAY			
31	41	09 COARSE SAND 15 CRS GRAVEL			
41	65	01 CLAY			
65	140	07 FINE SAND 08 MEDIUM SAND			
140	168	14 MED GRAVEL 15 CRS GRAVEL			
168	173	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/22/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/23/93 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmuth*