

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number
 COUNTY: 029 FORD NW 1/4 SW 1/4 NW 1/4 : 33 : T 26 S : R 24 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 2 MILES EAST OF DODGE CITY.

2 WATER WELL OWNER: OLD DODGE FEEDYARD Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: R.R.1, BOX 136
 City, State, ZIP code : DODGE CITY, KS 67801- Application Number: 31241

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

	NW	NE	
X			
W			E
	SW	SE	

4 DEPTH OF COMPLETED WELL 185 ELEVATION:
 Depth(s) Groundwater Encountered 1. 116 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 116 ft. below land surface measured on mo/day/yr 04/25/91
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 10 in. to 185 ft., and in. to ft.
 WELL WATER TO BE USED AS: 03 FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 185 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 155 ft. to 185 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 185 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 6 ft. to 20 ft., From 93 ft. to 105 ft., From ft. to ft.
 What is the nearest source of possible contamination: 09 FEEDYARD
 Direction from well? SURROUNDING AREA How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	1	01 CLAY			
1	20	01 CLAY 31 CALICHE			
20	35	01 CLAY 23 SANDSTONE			
35	50	07 FINE SAND 08 MEDIUM SAND 14 MED GRAVEL			
50	58	23 SANDSTONE			
58	65	07 FINE SAND 08 MEDIUM SAND 14 MED GRAVEL			
65	85	01 CLAY 04 SANDY CLAY			
85	94	01 CLAY			
94	100	07 FINE SAND 08 MEDIUM SAND			
100	113	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/06/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/15/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) Douglas A. Henkle

