

1 LOCATION OF WATER WELL: COUNTY: FORD Fraction: SW 1/4 NE 1/4 SE 1/4 Section Number 34 Township Number 26 Range Number 24

Distance and direction from nearest town or city street address of well if located within city?

2 WATER WELL OWNER: KANSAS SOLDIERS HOME
 RR#, St. Address, Box #: 101 PERSHING Board of Agriculture, Division of Water Resources
 City, State, ZIP code: FORT DODGE, KS 67843-0128 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	NW	NE	
Mile			
			E
	SW	SE	X

4 DEPTH OF COMPLETED WELL 220 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 58 ft. below land surface measured on no/day/yr 11/13/92
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8 in. to 220 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: MONITORING

Was a chemical/bacteriological sample submitted to department? No;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 4 in. to 220 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 40 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 180 ft. to 220 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 220 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY			
20	40	CLAY CALACHIE ROCK			
40	60	CLAY CALACHIE ROCK SAND ROCK LAYER			
60	80	FINE - MED SAND			
80	95	FINE - MED SAND SMALL GRAVEL			
95	130	CLAY FINE SAND IN LAYERS			
130	155	FINE SAND			
155	160	CLAY			
160	170	FINE - MED SAND			
170	215	MED-COARSE SAND SMALL GRAVEL VERY LOOSE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 11/13/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 12/16/92 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joseph Crick*

(Continued)

1 LOCATION OF WATER WELL: COUNTY: FORD Fraction: SW 1/4 NE 1/4 SE 1/4 Section Number 34 Township Number T 26 S Range Number R 24 W

2 WATER WELL OWNER: KANSAS SOLDIERS HOME
 RR#, St. Address, Box #: 101 PERSHING Board of Agriculture, Division of Water Resources
 City, State, ZIP code: FORT DODGE, KS 67843-0128 Application Number:

FROM	TO	LITHOLOGIC LOG
215	220	CLAY MED-COARSE SAND SMALL GRAVEL
220	230	CLAY
230	240	BLUE SHALE