

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: FORD SW 1/4 SW 1/4 SW 1/4 34 T 26 S R 25 W

Distance and direction from nearest town or city street address of well if located within city?
DODGE CITY - ON 14TH ST. 1 1/2 M. WEST ON MARSHALL ST.

2 WATER WELL OWNER: MORGISON, CHRIS
R.R. St. Address, Box #: 706 MINNEOLA ROAD Board of Agriculture, Division of Water Resources
City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:
4 DEPTH OF COMPLETED WELL 185 ELEVATION: 0
Depth of Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
WELL'S STATIC WATER LEVEL 33 ft. below land surface measured on mo/day/yr 04/15/96
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 95 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 9 in. to 185 ft. and in. to 0 ft.
WELL WATER TO BE USED AS: DOMESTIC
Was a chemical/bacteriological sample submitted to department? No:
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 185 ft. Dia in. to 0 ft. Dia in. to 0 ft.
Casing height above land surface 12 in. weight 200 lbs/ft. Wall thickness or gauge No. 21
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 180 ft. From 0 ft. to 0 ft.
From 0 ft. to 0 ft. From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 40 ft. to 185 ft. From 0 ft. to 0 ft.
From 0 ft. to 0 ft. From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout intervals: From 5 ft. to 40 ft. From 0 ft. to 0 ft. From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE - NEW SITE
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY COARSE SAND			
20	40	COARSE SAND GRAVEL CLAY			
40	60	CLAY FINE SAND IN LAYERS			
60	80	CLAY FINE - MED SAND SMALL GRAVEL			
80	100	FINE - MED SAND SMALL GRAVEL			
100	120	FINE - MED SAND SMALL GRAVEL CLAY LAYERS			
120	180	COARSE SAND SMALL GRAVEL MEDIUM SAND			
180	200	CLAY MED-COARSE SAND CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on mo/day/year 04/17/96 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 179 This Water Well Record was completed on mo/day/yr 04/30/96
Signed the business name of JOE'S WELL SERVICE, INC. by signature *Joe's Well Service*