


1 LOCATION OF WATER WELL: County: Ford		Fraction SE 1/4 SE 1/4 SW 1/4		Section Number 26	Township Number T 26 S	Range Number R 25 EW				
Distance and direction from nearest town or city street address of well if located within city? Approx. 110' S & 565' E of the SE Corner of Trail & Santa Fe Streets, Dodge City, KS										
2 WATER WELL OWNER: RR#, St. Address, Box # : Dodge City Cooperative Exchange 710 West Trail Street, Box 610 City, State, ZIP Code : Dodge City, Kansas 67801		52905124 MW-5 Board of Agriculture, Division of Water Resources Application Number:								
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 27.5 ft. ELEVATION: Approx. Surface Elev. 2482 Depth(s) Groundwater Encountered 1. 17 ft. 2. _____ ft. 3. _____ ft. WELL'S STATIC WATER LEVEL 19.2 ft. below land surface measured on mo/day/yr 03/07/91 Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm Est. Yield N/A gpm: Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 8.25 in. to 27.5 ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only (10) Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes _____ No X ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes _____ No X								
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued _____ Clamped _____ (2) PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded _____ Blank casing diameter 2 in. to 12 ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft. Casing height above land surface -3 in., weight _____ lbs./ft. Wall thickness or gauge No. Schedule 40 TYPE OF SCREEN OR PERFORATION MATERIAL: (7) PVC 10 Asbestos-cement 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) _____ 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot (3) Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 12 ft. to 27 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 10 ft. to 27.5 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.										
6 GROUT MATERIAL: (1) Neat cement 2 Cement grout (3) Bentonite 4 Other _____ Grout Intervals: From 0 ft. to 8 ft., From 8 ft. to 10 ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage (16) Other (specify below) Removed UST Direction from well? West/Northwest How many feet? 850										
FROM		TO		LITHOLOGIC LOG			FROM	TO	PLUGGING INTERVALS	
0		0.5		Asphalt						
0.5		2.5		Fill (Lean Clay) Brown						
2.5		7.5		Lean Clay with Sand Brown						
7.5		11.5		Silty Sand						
11.5		20.5		Fine to Coarse Sand with Trace of Gravel, Brown						
20.5		27.5		Fine to Coarse Sand with Gravel						
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 03/05/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 5-29-91 under the business name of Terracon Consultants, Inc. by (signature) <i>Steve Fischer</i>										