

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Ford</b>	Fraction <b>NW 1/4 NW 1/4 SE 1/4</b>	Section number <b>#28</b>	Township number <b>T #26</b>	Range number <b>S R #25</b>	<b>X/W</b>
2. Distance and direction from nearest town or city: <b>1/2 mile west of Dodge City, Kansas</b> Street address of well location if in city:				3. Owner of well: <b>Dan Richenborn</b> R.R. or street: <b>West Park</b> City, state, zip code: <b>Dodge City, Kansas 67801</b>			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile				Sketch map: <b>OWELL</b> <b>HOUSE SITE</b> <b>DRIVE</b> <b>Road</b>			
5. Type and color of material				From	To	6. Bore hole dia. <b>8</b> in. Completion date <b>4-19-75</b> Well depth <b>165</b> ft.	
<b>Top soil &amp; coarse sand</b>				<b>0</b>	<b>15</b>	7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
<b>Coarse sand &amp; clay</b>				<b>15</b>	<b>30</b>	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
<b>Clay &amp; fine sand</b>				<b>30</b>	<b>45</b>	9. Casing: Material <b>RMP</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <b>12</b> in. RMP <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. <b>5</b> in. to <b>165</b> ft. depth; Wall Thickness _____ inches or Dia. _____ in. to _____ ft. depth; gage No. <b>250</b>	
<b>Fine sand &amp; clay layers</b>				<b>45</b>	<b>60</b>	10. Screen: Manufacturer's name <b>Sunflower</b>	
<b>Fine to medium sand</b>				<b>60</b>	<b>75</b>	Type <b>RMP</b> Dia. <b>5"</b> Slot <b>1/8"</b> Length <b>20 Ft.</b> Set between <b>140</b> ft. and <b>160</b> ft. _____ ft. and _____ ft. Gravel pack? <b>yes</b> Size range of material <b>1/4"</b>	
<b>Fine sand</b>				<b>75</b>	<b>90</b>	11. Static water level: <b>12</b> ft. below land surface Date <b>4-19-75</b> mo./day/yr.	
<b>Fine sand &amp; medium</b>				<b>90</b>	<b>105</b>	12. Pumping level below land surfaces: <b>12</b> ft. after <b>2</b> hrs. pumping <b>70</b> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>125</b> g.p.m.	
<b>Medium to coarse sand</b>				<b>105</b>	<b>120</b>	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____	
<b>Coarse sand</b>				<b>120</b>	<b>170</b>	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <b>12</b> inches above grade	
<b>Clay &amp; blue shale</b>				<b>170</b>	<b>175</b>	15. Well grouted? <b>yes</b> With: <input checked="" type="checkbox"/> Negt cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>5</b> ft. to <b>30</b> ft.	
<b>BRock 170'</b>						16. Nearest source of possible contamination: <b>None</b> ft. _____ Direction <b>that we know of</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
<b>12' 750 gal tank</b>						17. Pump: <b>Not installed</b> Manufacturer's name <b>Flint &amp; Walling</b> Model number <b>10BK9</b> HP <b>1</b> Volts <b>230</b> Length of drop pipe <b>105</b> ft. capacity <b>19</b> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>JOE'S WELL SERVICE</b> <b>179</b> Business name License No. Address <b>Box 174 Cimarron, Ks</b> Signed <b>Jay L. Crick</b> Date <b>5-25-75</b> Authorized representative	
18. Elevation:		19. Remarks: <b>New building site</b> <b>711</b>					
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5