

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SW 1/4 SW 1/4 SE 1/4 31 T 26 S R 25 E

Distance and direction from nearest town or city street address of well if located within city?
 FROM DODGE CITY - 3 MILES WEST ON BRESON ROAD

2 WATER WELL OWNER: KONECNY, RICK
 RR#, St. Address, Box #: BOX 88 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: CINTRON, KS 67835- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

4 DEPTH OF COMPLETED WELL 225 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 65 ft. below land surface measured on mo/day/yr 07/24/06
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 75 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 225 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 225 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 180 ft., From 0 ft. to 0 ft.
 From 200 ft. to 220 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 225 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 37 FIN-COAR SAN 06 SMALL GRAVEL			
20	100	37 FIN-COAR SAN 38 SMAL-MED GRA			
100	120	37 FIN-COAR SAN 38 SMAL-MED GRA 14 WHITE CLAY			
120	140	14 WHITE CLAY 10 FINE-MEDSAND			
140	180	10 FINE-MEDSAND 14 WHITE CLAY 19 LAYERS			
180	200	32 TAN CLAY			
200	220	22MED-COAR SAND 38 SMAL-MED GRA			
220	240	32 TAN CLAY 26 RED CLAY			
240	260	26 RED CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/25/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 08/02/06 by (signature) *Justin Creek*
 under the business name of JOE'S WELL SERVICE, INC.