

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SW 1/4 SW 1/4 SE 1/4 28 T 26 S R 25 W

Distance and direction from nearest town or city street address of well if located within city?

10874 W. PARK DODGE CITY, KS 67801-

2 WATER WELL OWNER: REICHENBORN, DAN
 RR#, St. Address, Box #: 10874 W. PARK Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number: FO-19

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

WELL'S STATIC WATER LEVEL 42 ft. below land surface measured on mo/day/yr 06/07/06
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 450 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 15 in. to 183 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 10 in. to 183 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. *See 40*
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 120 ft. to 180 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 24 ft. to 183 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 24 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? NORTHWEST How many feet? 10

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY 37 FIN-COAR SAN			
20	40	18 LARGE 09 GRAVEL 05 CLAY			
40	60	32 TAN CLAY			
60	80	32 TAN CLAY 10 FINE-MEDSAND 19 LAYERS			
80	100	37 FIN-COAR SAN			
100	120	37 FIN-COAR SAN 06 SMALL GRAVEL			
120	160	37 FIN-COAR SAN 23 MEDIUM 09 GRAVEL			
160	180	37 FIN-COAR SAN 09 GRAVEL 05 CLAY			
180	200	16 GRAY CLAY 07 BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/26/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 07/10/06 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Justin Creek*