

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction NE 1/4 NE 1/4 SW 1/4 Section Number 28 Township Number T 26 S Range Number R 25 E
COUNTY: FORD

Distance and direction from nearest town or city street address of well if located within city?
TRACK 16 RINEY ADDITION

2 WATER WELL OWNER: GOFF, MARSHALL
RR#, St. Address, Box #: 10842 W. PARK
City, State, ZIP code: DODGE CITY, KS 67801- Board of Agriculture, Division of Water Resources
Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	NW	NE
W	X	E
SW	SE	

4 DEPTH OF COMPLETED WELL 165 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 22 ft. below land surface measured on mo/day/yr 08/14/97
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 50 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 9 in. to 165 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 165 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 140 ft. to 160 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 35 ft. to 165 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout Intervals: From 0 ft. to 35 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE - NEW SITE
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	4	TOPSOIL			
4	25	MED-COARSE SAND GRAVEL			
25	50	CLAY			
50	80	FINE SAND			
80	100	FINE SAND COARSE SAND			
100	120	MED-COARSE SAND SMALL GRAVEL			
120	160	COARSE SAND FINE - MED SAND			
160	165	CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/14/97 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 08/25/97
under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*