

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: FORD NE 1/4 SE 1/4 NE 1/4 30 T 26 S R 25

Distance and direction from nearest town or city street address of well if located within city?  
 FROM DODGE CITY - 3 1/2 WEST OF DODGE CITY ON HIGHWAY 50

2 WATER WELL OWNER: BAYLESS, DALE  
 RR#, St. Address, Box #: 10652 US HIGHWAY 50 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

|   |    |    |    |
|---|----|----|----|
| 1 | 2  | 3  | 4  |
| 5 | 6  | 7  | 8  |
| 9 | 10 | 11 | 12 |

WELL'S STATIC WATER LEVEL 96 ft. below land surface measured on mo/day/yr 10/01/09  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 40 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 10 in. to 245 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC  
 Blank casing diameter 5 in. to 245 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 180 ft. to 240 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 245 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE  
 Direction from well? How many feet? 0

| FROM | TO  | LITHOLOGIC LOG                                | FROM | TO | PLUGGING INTERVALS |
|------|-----|---|------|----|--------------------|
| 0    | 20  | 01 TOPSOIL 32 TAN CLAY                        |      |    |                    |
| 20   | 40  | 32 TAN CLAY 37 FIN-COAR SAN 06 SMALL GRAVEL   |      |    |                    |
| 40   | 60  | 37 FIN-COAR SAN 38 SMAL-MED GRA 24 THINROCLAY |      |    |                    |
| 60   | 80  | 37 FIN-COAR SAN 06 SMALL GRAVEL 17 CLAY LAYER |      |    |                    |
| 80   | 100 | 02 FINE SAND 17 CLAY LAYERS                   |      |    |                    |
| 100  | 120 | 02 FINE SAND                                  |      |    |                    |
| 120  | 140 | 10 FINE-MEDSAND                               |      |    |                    |
| 140  | 160 | 10 FINE-MEDSAND 04 COARSE SAND                |      |    |                    |
| 160  | 180 | 37 FIN-COAR SAN                               |      |    |                    |
| 180  | 220 | 37 FIN-COAR SAN 38 SMAL-MED GRA               |      |    |                    |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/02/09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/16/09 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Juliett Creek*

DEL  
 5/17/2010

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

| 1 LOCATION OF WATER WELL: | Fraction             | Section Number | Township Number | Range Number |
|---------------------------|----------------------|----------------|-----------------|--------------|
| COUNTY: FORD              | NE 1/4 SE 1/4 NE 1/4 | 30             | T 26 S          | R 25 E       |

|                          |                       |  |
|--------------------------|-----------------------|--|
| 2 WATER WELL OWNER:      | BAYLESS, DALE         | Board of Agriculture, Division of Water Resources<br>Application Number: |
| RR#, St. Address, Box #: | 10652 US HIGHWAY 50   |  |
| City, State, ZIP code    | DODGE CITY, KS 67801- |  |

| FROM | TO  | LITHOLOGIC LOG                          |
|------|-----|---|
| 220  | 240 | 37 FIN-COAR SAN 38 SMAL-MED GRA 05 CLAY |
| 240  | 260 | 32 TAN CLAY 11 BROWN CLAY               |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/02/09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 10/16/09 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Jessie Creek*