

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

ADD

770061  
CITY

1. Location of well:		County <b>Ford</b>	Fraction <b>SE 1/4 SE 1/4 NE 1/4</b>	Section number <b>#1</b>	Township number <b>T #26</b>	Range number <b>S R #26</b>	<b>X/W</b>
2. Distance and direction from nearest town or city: <b>4 miles west and 3 1/2 north of Dodge City, Kansas 67801</b> Street address of well location if in city:				3. Owner of well: <b>Alfred Giessel</b> R.R. or street: City, state, zip code: <b>Spearville, Kansas 67876</b>			
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile		Sketch map: 		6. Bore hole dia. <b>8</b> in. Completion date <b>2-22-77</b> Well depth <b>195</b> ft.			
5. Type and color of material		From	To	7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
Top soil & Clay		0	15	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other			
Clay		15	45	9. Casing: Material <b>RMP</b> Height: Above or below <b>12</b> in. Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <b>12</b> in. RMP <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>5</b> in. to <b>195</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>250</b>			
Clay & gyp rock		45	75	10. Screen: Manufacturer's name <b>Sunflower</b> Type <b>RMP</b> Dia. <b>5</b> " Slot/size <b>1/8</b> " Length <b>20</b> ft. Set between <b>170</b> ft. and <b>190</b> ft. ft. and <input type="checkbox"/> ft. Gravel pack? <b>yes</b> Size range of material <b>1/4</b> "			
Clay & medium sand		75	90	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>89</b> ft. below land surface Date <b>2-22-77</b>			
Medium sand		90	120	12. Pumping level below land surfaces: <b>95</b> ft. after <b>1</b> hrs. pumping <b>20</b> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>25</b> g.p.m.			
Medium sand & white rock (loose)		120	135	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>			
White rock & medium sand		135	150	14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <b>12</b> inches above grade			
Medium sand & clay		150	165	15. Well grouted? <b>yes</b> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>7</b> ft. to <b>15</b> ft.			
Medium to coarse sand		165	195	16. Nearest source of possible contamination: <b>None</b> ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
Medium sand & clay		195	210	17. Pump: Manufacturer's name <b>Aermotor</b> Model number <b>SD12-100</b> HP <b>1</b> Volts <b>230</b> Length of drop pipe <b>168</b> ft. capacity <b>12</b> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
Clay & blue shale		210	225	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Joe's Well Service</b> <b>179</b> Business name License No. Address <b>Box 174 Cimarron, Ks.</b> Signed <b>Larry Crick</b> Date <b>8-25-76</b> Authorized representative			
18. Elevation:		19. Remarks: <b>New building site</b> <b>2612</b> <b>210</b> <b>770061</b>					
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5