


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Ford	Fraction SW 1/4 NW 1/4 NW 1/4	Section number 4	Township number T 26 S R 26 E W
2. Distance and direction from nearest town or city: 3 mi north of Howell, Kansas Street address of well location if in city:			3. Owner of well: Rex Stanley R.R. or street: RFD 2 City, state, zip code: Dodge City, Kansas		
4. Locate with "X" in section below: 		Sketch map:		6. Bore hole dia. 9 in. Completion date 8-10-79 Well depth 168 ft.	
5. Type and color of material		From	To	7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
Surface		0	3	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Brown and calciche clay mixed		3	67	9. Casing: Material plastic Height: Above or below Threaded glued Surface 18 in. RMP Styrene/c Weight 1.8 lbs./ft.	
Brown sandy clay with rock layers		67	73	Dia. 5 in. to 168 ft. depth Wall thickness: inches or Dia. 5 in. to 168 ft. depth gage No. 250	
Good brown gravel(dry)		73	78	10. Screen: Manufacturer's name Jess & Lowell Type sawed Dia. 5 Slot/gauze .60 Length 30 Set between 138 ft. and 168 ft. Gravel pack? yes Size range of material 3/8 down	
Hard rock		78	80	11. Static water level: 111 ft. below land surface Date 3-8-79	
Fine to med. sand with cemented gravel layers		80	89	12. Pumping level below land surfaces: NA ft. after hrs. pumping g.p.m. after hrs. pumping g.p.m. Estimated maximum yield NA pump g.p.m.	
Med. sand and gravel		89	101	13. Water sample submitted: mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date	
Sandy clay		101	106	14. Well head completion: 18 Pitless adapter 18 Inches above grade	
Fine to med. sand		106	126	15. Well grouted? yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.	
Clay		126	132	16. Nearest source of possible contamination: field ft. Direction Type Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Fine to med. sand		132	138	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name windmill cly. Model number 147 HP ? Volts ? Length of drop pipe 147 ft. capacity ? g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input checked="" type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
Clay		138	141	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Ace-Hi International 190 Business name License No. Address Dodge City, Kansas Signed Carl G. Jett Date 9-10-79 Authorized representative	
Fine to med. sand & gravel with clay layers		141	163		
Brown clay		163	171		
Med. sand		171	179		
Med. sand and gravel with 15% clay		179	191		
Clay		191	197		
Med. sand and gravel with 15% clay		197	228		
Gray shale		228	238		
Rock 228					
111					
117 sat. th.					
in g					
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:		20. Water well contractor's certification:		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	1060 2655 228 2327		Ace-Hi International 190 Business name License No. Address Dodge City, Kansas Signed Carl G. Jett Date 9-10-79 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5