

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 029 FORD | SE 1/4 SW 1/4 SW 1/4 | 16 | T 26 S | R 26 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1/4 MILE NORTH AND 6 3/4 MILES WEST OF DODGE CITY.

2 WATER WELL OWNER: JANET BEVER
 RR#, St. Address, Box #: 513 ANDREW Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number: FO 28

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 170 ELEVATION:
 Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL 20 ft. below land surface measured on mo/day/yr 03/22/91
 Pump testdata: Well water was 72 ft. after 4 hours pumping 1746 gpm
 Estimated Yield 1700 gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 24 in. to 170 ft., and in. to ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 170 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 97 ft. to 167 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 170 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From ft. to 30 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? EAST How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	1	01 CLAY			
1	5	04 SANDY CLAY 07 FINE SAND			
5	21	07 FINE SAND 08 MEDIUM SAND 14 MED GRAVEL			
21	30	04 SANDY CLAY			
30	48	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
48	57	04 SANDY CLAY			
57	60	01 CLAY			
60	75	01 CLAY 07 FINE SAND 08 MEDIUM SAND			
75	89	06 VERY FN SAND 07 FINE SAND 08 MEDIUM SAND			
89	96	01 CLAY 07 FINE SAND 08 MEDIUM SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/24/01 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/09/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichmuth*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 029 FORD	SE 1/4 SW 1/4 SW 1/4	16	T 26 S	R 26 W

2 WATER WELL OWNER:	JANET BEVER	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	513 ANDREW	Application Number: FO 28
City, State, ZIP code :	DODGE CITY, KS 67801-	

FROM	TO	LITHOLOGIC LOG
96	136	07 FINE SAND 08 MEDIUM SAND 01 CLAY
136	167	07 FINE SAND 08 MEDIUM SAND 28 ROCK
167	170	19 SHALE
170	180	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/24/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/09/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Leckmuth*