

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction $\frac{1}{4}$ SE $\frac{1}{4}$ NE $\frac{1}{4}$ Section Number 20 Township Number 26 Range Number 26
 COUNTY: FORD

Distance and direction from nearest town or city street address of well if located within city?
 FROM HOWELL - ON BLACK TOP 1 MILE SOUTH ON WEST SIDE OF ROAD

2 WATER WELL OWNER: NICHOLS, KELLY
 RR#, St. Address, Box #: ROUTE #2 BOX 322 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
NE	SE	SW	NW
			X

4 DEPTH OF COMPLETED WELL 205 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 22 ft. below land surface measured on mo/day/yr 02/01/93
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 75 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 8 in. to 205 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 205 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 180 ft. to 200 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 205 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 5 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? SOUTHEAST How many feet? 10

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL FINE - MED SAND MED-COARSE SAND			
20	40	COARSE SAND LARGE GRAVEL			
40	60	CLAY FINE SAND IN LAYERS			
60	80	CLAY FINE SAND IN LAYERS			
80	100	CLAY FINE - MED SAND IN LAYERS			
100	120	FINE SAND CLAY LAYERS			
120	140	CLAY FINE SAND IN LAYERS			
140	150	FINE - MED SAND			
150	180	MED-COARSE SAND SMALL GRAVEL			
180	205	CLAY ROCK LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/02/93 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 02/23/93
 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*