

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

18,603

1 LOCATION OF WATER WELL: County: Ford		Fraction 1/4 SE 1/4 SE 1/4 NW 1/4		Section Number 33	Township No. T 26 S	Range Number R 26 ☐ E ☒ W							
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 2 3/4 south & 1/2 east of Howell				Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m									
2 WATER WELL OWNER: Eldon & Linda Dirks RR#, Street Address, Box #: P.O. Box 885 City, State, ZIP Code : Ulvsses, Ks. 67880-0885													
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="width:100%; text-align: center; border-collapse: collapse;"> <tr> <td style="width:25%;">NW</td> <td style="width:25%;">NE</td> <td style="width:25%;">SW</td> <td style="width:25%;">SE</td> </tr> <tr> <td></td> <td></td> <td>X</td> <td></td> </tr> </table> S -----1 mile-----		NW	NE	SW	SE			X		4 DEPTH OF COMPLETED WELL 182 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL 102 ft. below land surface measured on mo/day/yr. 5-3-11..... Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD. NA..... gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter 30 in. to 182 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No			
NW	NE	SW	SE										
		X											
5 TYPE OF CASING USED: ☒ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter .16 in. to 182 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 18 in., Weight Sch 40 lbs./ft., Wall thickness or gauge No. TYPE OF SCREEN OR PERFORATION MATERIAL: ☒ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☒ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 182 ft. to 162 ft., From ft. to ft. From 155 ft. to 115 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 182 ft., From ft. to ft. From ft. to ft., From ft. to ft.													
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From ft. to ft., From 20 ft. to 0 ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well ☒ None Direction from well Distance from well													
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS								
0	7	Top soil	147	155	clay w/lime								
7	30	Sand	155	165	Sand & little clay								
30	75	Sand & gravel	165	168	Sand								
75	90	Sand & gravel w/little clay	168	180	Lime & clay								
90	105	Sand	180	182	Clay & little lime								
105	120	Sand & gravel											
120	132	Sand & gravel little cemented sand											
132	136	Coarse gravel											
136	143	Clay w/lime											
143	147	Sand											
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 5-3-11..... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134..... This Water Well Record was completed on (mo/day/year) 6-3-11..... under the business name of Rosencrantz-Bemis by (signature) <i>Gora Alapa</i>													
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY</u> and <u>PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each <u>constructed</u> well. Visit us at http://www.kdheks.gov/waterwell/index.html .													