



*The  
Professionals*

# MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation  
and Domestic  
Water Systems  
Complete Installation  
and Repairing

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

John Jillie  
Gray County  
5/15/95

Location: NW $\frac{1}{4}$  16-26-27  
From Cimarron Bridge - 1 Mile South,  
3 $\frac{1}{2}$  Miles East,  $\frac{1}{4}$  Mile North &  $\frac{1}{4}$  Mile West  
Offset 125' South

Static Water Level - About 30'

## Test #1

0' to 2' ~~04~~ Top soil  
2' to 4' ~~04~~ Brown sandy clay - loose  
4' to 10' ~~07~~ Fine to medium sand and gravel  
- loose  
10' to 37 $\frac{1}{2}$  Medium coarse gravel  
37' to 64' ~~04~~ Brown sandy clay - small sand stone  
streak  
64' to 66' ~~07~~ Fine to medium sand - loose  
66' to 95' ~~04~~ Brown sandy clay  
95' to 110' ~~07~~ Fine sand - loose  
110' to 117' - Brown sandy clay  
117' to 126' ~~04~~ Brown sandy clay - small strip  
of fine sand  
126' to 136' ~~07~~ Fine to medium sand - loose  
136' to 155' ~~07~~ Fine to medium sand and gravel  
- small yellow rock mixed - loose  
155' to 174' ~~14~~ Medium coarse gravel - loose  
174' to 182' ~~04~~ Brown yellow clay  
182' to 190' ~~07~~ Shale - hard pull down