

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 NW 1/4 SW 1/4	33	T 26 S	R 27 W

Distance and direction from nearest town or city street address of well if located within city?
FROM CIMARRON, KS. - 4 SOUTH ON HIGHWAY 23 & 3 MILES EAST

2 WATER WELL OWNER:	VERN GOETZ	Wall #2
RR#, St. Address, Box #:	BOX 1317	Board of Agriculture, Division of Water Resources
City, State, ZIP code :	DODGE CITY, KS 67801-	Application Number: 26800

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 243 ELEVATION: 0
--	--

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 102 ft. below land surface measured on mo/day/yr 01/06/95
Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 215 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

E Bore Hole Diameter 17 in. to 243 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: IRRIGATION

Was a chemical/bacteriological sample submitted to department? No;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC	CASING JOINTS: GLUED
----------------------------------	----------------------

Blank casing diameter 10 in. to 243 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 130 ft. to 230 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 243 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL: BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: IRRIGATION WELL

Direction from well? SOUTH

How many feet? 300

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	12	TOPSOIL SANDY CLAY			
12	22	FINE SAND			
22	30	SANDY CLAY			
30	50	FINE SAND CLAY			
50	71	MEDIUM SAND FINE SAND			
71	80	CLAY SAND			
80	141	MED-COARSE SAND GRAVEL CLAY			
141	173	FINE SAND BROWN CLAY			
173	192	MEDIUM SAND			
192	215	TAN IN COLOR CLAY FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/08/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/08/95 under the business name of JOE'S WELL SERVICE, INC.
--

by (signature) *Joe's Well Service*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: GRAY	SE 1/4 NW 1/4 SW 1/4	33	T 26 S	R 27 W

2 WATER WELL OWNER:	VERN GOETZ	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #:	BOX 1317	Application Number: 26800
City, State, ZIP code :	DODGE CITY, KS 67801-	

FROM	TO	LITHOLOGIC LOG
215	224	CLAY MEDIUM SAND CLAY
224	233	YELLOW CLAY
233	243	BLUE SHALE