

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction SW 1/4 NW 1/4 SE 1/4 Section Number 9 Township Number T 26 S Range Number R 27 W
COUNTY: GRAY

Distance and direction from nearest town or city street address of well if located within city?
FROM CINARROW - ON HIGHWAY 50 - 3 1/2 MILES EAST

2 WATER WELL OWNER: KINDEWATER, DENNIS
RR#, St. Address, Box #: BOX 1027 Board of Agriculture, Division of Water Resources
City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	NW	NE
W		
E	SW	SE

4 DEPTH OF COMPLETED WELL 245 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
WELL'S STATIC WATER LEVEL 168 ft. below land surface measured on mo/day/yr 05/14/96
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 75 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 10 in. to 245 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: DOMESTIC
Was a chemical/bacteriological sample submitted to department? No;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLOUED
Blank casing diameter 6 in. to 245 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 200 ft. to 240 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 30 ft. to 245 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL: BENTONITE
Grout intervals: From 5 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE - NEW SITE
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL CLAY FINE SAND			
20	40	FINE SAND CALACHIE SANDSTONE			
40	60	FINE SAND ROCK LAYERS MED-COARSE SAND			
60	80	MED-COARSE SAND CLAY LAYERS			
80	100	FINE - MED SAND CLAY LAYERS			
100	120	FINE SAND			
120	140	FINE - MED SAND CLAY LAYERS			
140	160	CLAY LAYERS FINE SAND			
160	180	FINE SAND			
180	200	FINE SAND CLAY LAYERS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 06/05/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 08/12/96 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joe's Well Service*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction SW 1/4 NE 1/4 SE 1/4 Section Number 9 Township Number T 26 S Range Number R 27 W
COUNTY: GRAY

2 WATER WELL OWNER: KINDEWATER, DENNIS
RR#, St. Address, Box #: BOX 1027 Board of Agriculture, Division of Water Resources
City, State, ZIP code: DODGE CITY, KS 67801- Application Number:

FROM	TO	LITHOLOGIC LOG
200	220	FINE SAND COARSE SAND SMALL GRAVEL
220	245	MED-COARSE SAND SMALL GRAVEL ROCK
245	260	ROCK LAYERS BLUE SHALE