

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Gray	Fraction NE 1/4 NE 1/4 NW 1/4	Section number #24	Township number T #26	Range number S R #27 E 1/4 NW
2. Distance and direction from nearest town or city: 1 mile south, 6 1/2 miles east of Cimarron, Ks. Street address of well location if in city:			3. Owner of well: John Schartz R.R. or street: City, state, zip code: Cimarron, Kansas 67835			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 6 in. Completion date 6-16-76 Well depth 210 ft.		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
				8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Off field water ☐ Other		
				9. Casing: Material RMP Height: Above or BELOW Threaded ☐ Welded ☐ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 210 ft. depth Well thickness inches or Dia. ☐ in. to ☐ ft. depth gage No. 250		
				10. Screen: Manufacturer's name Sancler Type RMP Dia. 5" Slot 1/8" Length 20 ft. Set between 105 ft. and 205 ft. Gravel pack yes Size range of material 1/4"		
5. Type and color of material		From	To	11. Static water level: 65 ft. below land surface Date 6-16-76		
Top soil & fine to coarse sand		0	15	12. Pumping level below land surfaces: 66 ft. after 1 hrs. pumping 50 g.p.m. 105 ft. after 1 hrs. pumping 50 g.p.m. Estimated maximum yield 90 g.p.m.		
Coarse sand		15	30	13. Water sample submitted: yes No no Date 6-16-76		
Coarse sand & clay		30	45	14. Well head completion: ☒ Pitless adapter 21 inches above grade		
Clay		45	90	15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
Clay & fine sand		90	105	16. Nearest source of possible contamination: Feed ft. 100 Direction North Type lot Well disinfected upon completion? ☒ Yes ☐ No		
Fine sand		105	150	17. Pump: Not installed Manufacturer's name First & Walling Model number 20016 HP 2 Volts 230 Length of drop pipe 150 ft. capacity 19 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Fine to coarse sand		150	165	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. JOE'S WELL SERVICE 179 Business name License No. Address Box 174 Cimarron, Ks. Signed Joe Schartz Date 7-6-76 Authorized representative		
Coarse sand		165	197			
Clay & blue shale		197	210			
(Use a second sheet if needed)						
18. Elevation:	19. Remarks:					
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5