


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County GRAY	Fraction SW 1/4 NE 1/4 NE 1/4	Section number 25	Township number T 26 S	Range number R 27 E
2. Distance and direction from nearest town or city: Going South of Ingalls, Mo. to the 2ND Curve, 1 East, 1 3/4 North, 1/4 West, 30ft East of Piv		3. Owner of well: Vath Farms Street address of well location if in city: c/o Bob Vath Cimarron, Ks 67835				
4. Locate with "X" in section below: 		Sketch map:		6. Bore hole dia. 26 in. Completion date 3-30-76 Well depth 247 ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material Steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 36.87 lbs./ft. Dia 16 in. to 248 ft. depth Well Thickness: inches or Dia. ☐ in. to ☐ ft. depth gauge No. ☐		
				10. Screen: Manufacturer's name Johnson Division Type Galv. Dia. 16" Slot/gauze 100 Length 20' Set between 180 ft. and 200 ft. Perf. 120-180 ft. and 200-247 ft. Gravel pack? Yes Size range of material 2" Down		
				11. Static water level: ☐ mo./day/yr. 91 ft. below land surface Date 3-25-76		
				12. Pumping level below land surfaces: 99 ft. after 3 hrs. pumping 1525 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1500 g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. Yes ☒ No ☐ Date ☐		
				14. Well head completion: ☐ Pitless adapter 12 inches above grade		
				15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: n/a ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: Not installed Manufacturer's name PMC Peerless Pumps Model number 5577 HP 125 Volts ☐ Length of drop pipe 140 ft. capacity 1500 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter Wilson Drilling 208 Business name P.O. Box A Garden City, Ks License No. ☐ Address 3-30-76 Date ☐ Authorized representative Robert A. DePue				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

The
Professional

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Vath Farm
Gray County
1-15-76

Location: NE 25-26-27
Going South of Ingalls to the second curve, go
east 1 mile and 1-3/4 mile North, 1/4 west, 30
feet east of pivot

Static Water Level - 80'

Test # 1

0	1	Top Soil
1	6	Fine Sand
6	16	Brown Clay
16	70	Fine Sand
70	76	Brown Sandy Clay
76	95	Fine to Med. Sand & Gravel (Loose)
95	155	Med. Sand & Gravel (Loose)
155	203	Med. Coarse Gravel (Loose)
203	216	Brown Sandy Clay, Gravel Streaks
216	247	Fine to Med. Sand & Gravel mixed with rock (Tigh
247	263	Brown Sandy Clay
263	275	Shale (Hard)

T.D. - 247'