

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	SW 1/4 NE 1/4 NW 1/4	13	T 26 S	R 27 W

Distance and direction from nearest town or city street address of well if located within city?

FROM CIMARRON; APPX 5 3/4 MILES EAST & 1 MILE SOUTH

2 WATER WELL OWNER:	DAN MILLER	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	PO BOX 668	Application Number: GY-07
City, State, ZIP code :	CIMARRON, KS 67835-	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 165 ELEVATION: 0
	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \ X	WELL'S STATIC WATER LEVEL 73 ft. below land surface measured on mo/day/yr 06/26/07
	Pump test data: Well water was 143 ft. after 4 hours pumping 1073 gpm

1 NW NE	Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
---------	---

M i W E	Bore Hole Diameter 24 in. to 165 ft., and in. to 0 ft.
---------	--

l e SW SE	WELL WATER TO BE USED AS: 02 IRRIGATION
-----------	---

\ /	Was a chemical/bacteriological sample submitted to department? No ;
	If yes, mo/day/yr sample was submitted

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED

Blank casing diameter 16 in. to 165 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 124 ft. to 154 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 165 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTHEAST How many feet? 82

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	23	05 SAND 11 GRAVEL			
23	58	04 SANDY CLAY 20 LIMESTONE 05 SAND			
58	86	05 SAND 13 FINE GRAVEL 01 CLAY			
86	109	04 SANDY CLAY 05 SAND			
109	123	05 SAND 01 CLAY			
123	154	05 SAND 28 ROCK			
154	157	31 CALICHE			
157	160	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/21/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/24/07
under the business name of HENKLE DRILLING & SUPPLY by (signature) 