

1 LOCATION OF WATER WELL:	Fraction <i>BLK 441 Cimarron Land Company Addition</i>	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	NE 1/4 NW 1/4 SE 1/4	02	T 26 S	R 28 W

Distance and direction from nearest town or city street address of well if located within city?

1100 BLK OF N. MAIN ST. , KS -

2 WATER WELL OWNER: CITY OF CIMARRON
RR#, St. Address, Box #: PO BOX 467

Board of Agriculture, Division of Water Resources

City, State, ZIP code : CIMARRON, KS 67838-0467

Application Number: 16134 & GY34

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 335 ELEVATION: 0

Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

/ \					WELL'S STATIC WATER LEVEL 195 ft. below land surface measured on mo/day/yr 07/14/99
1	----- NW -----	----- NE -----			Pump testdata: Well water was 245 ft. after 4 hours pumping 708 gpm
M					Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
i	W -----	----- E			Bore Hole Diameter 24 in. to 335 ft., and in. to 0 ft.
1		X			WELL WATER TO BE USED AS: 05 PUB. WTR SUP
e	----- SW -----	----- SE -----			Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes
\ /					

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED

Blank casing diameter 16 in. to 335 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 63 lbs/ft. Wall thickness or gauge No. .375

TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 200 ft. to 250 ft., From 294 ft. to 330 ft.

From 270 ft. to 287 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 70 ft. to 335 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 02 CEMENT GROUT

Grout Intervals: From 0 ft. to 70 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTHEAST

How many feet? 36

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	6	04 SANDY CLAY 31 CALICHE 11 GRAVEL			
6	42	04 SANDY CLAY 31 CALICHE			
42	51	04 SANDY CLAY			
51	65	01 CLAY 20 LIMESTONE			
65	76	04 SANDY CLAY 20 LIMESTONE 05 SAND			
76	95	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
95	101	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
101	114	04 SANDY CLAY 05 SAND			
114	130	05 SAND 13 FINE GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/13/99 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/28/99 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Blk 4 Cimarron Land Company Addition	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	NE 1/4 NW 1/4 SE 1/4		02	T 26 S	R 28 W

2 WATER WELL OWNER: CITY OF CIMARRON
RR#, St. Address, Box #: PO BOX 467

Board of Agriculture, Division of Water Resources

City, State, ZIP code : CIMARRON, KS 67838-0467

Application Number: 16134 & GY34

LITHOLOGIC LOG		
130	140	04 SANDY CLAY 05 SAND
140	153	05 SAND 01 CLAY
153	159	04 SANDY CLAY 05 SAND
159	180	04 SANDY CLAY 36 GYP ROCK 05 SAND
180	190	01 CLAY
190	201	06 VERY FN SAND 07 FINE SAND 01 CLAY
201	220	05 SAND 01 CLAY
220	233	05 SAND 13 FINE GRAVEL 01 CLAY
233	239	01 CLAY 05 SAND
239	250	06 VERY FN SAND 07 FINE SAND 01 CLAY
250	270	01 CLAY 31 CALICHE
270	287	05 SAND 11 GRAVEL 28 ROCK
287	294	01 CLAY 05 SAND
294	302	07 FINE SAND 01 CLAY
302	330	28 ROCK 20 LIMESTONE 05 SAND
330	342	19 SHALE
342	360	19 SHALE 20 LIMESTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/13/99 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/28/99 under the business name of HENKLE DRILLING & SUPPLY

by (signature) *Bruce Reichmuth*