

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction COUNTY: 035 GRAY	SE 1/4 SE 1/4 SE 1/4	Section Number 02	Township Number T 26 S	Range Number R 28 W
---------------------------	------------------------------	----------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?  
, KS 67835-

2 WATER WELL OWNER: USD #102  
RR#, St. Address, Box #: PO BOX 489

Board of Agriculture, Division of Water Resources

City, State, ZIP code : CIMARRON, KS 67835-0489	Application Number: 38028
---	---------------------------

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 296 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
/ \ 1 M i e \ /	WELL'S STATIC WATER LEVEL 104 ft. below land surface measured on mo/day/yr 04/03/00 Pump testdata: Well water was 179 ft. after 4 hours pumping 1206 gpm Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 24 in. to 296 ft., and in. to 0 ft. WELL WATER TO BE USED AS: 02 IRRIGATION Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes
----- NW ----- NE ----- SW ----- SE ----- X -----	

5 TYPE OF BLANK CASING USED: 01 STEEL	CASING JOINTS: WELDED
Blank casing diameter 16 in. to 296 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219	
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL	
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT	

SCREEN PERFORATED INTERVALS:	From 231 ft. to 291 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
From 20 ft. to 294 ft., From 0 ft. to 0 ft.	
From 0 ft. to 0 ft., From 0 ft. to 0 ft.	

6 GROUT MATERIAL 03 BENTONITE	
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: NONE OBSERVED	
Direction from well? SOUTHEAST	How many feet? 78

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	22	01 CLAY 36 GYP ROCK			
22	30	04 SANDY CLAY 05 SAND			
30	48	05 SAND 13 FINE GRAVEL			
48	77	01 CLAY 04 SANDY CLAY			
73	85	05 SAND 13 FINE GRAVEL 01 CLAY			
85	96	01 CLAY			
96	111	05 SAND 13 FINE GRAVEL			
111	122	04 SANDY CLAY 05 SAND			
122	129	05 SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/28/00 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/01/00 under the business name of HENKLE DRILLING & SUPPLY	by (signature)
--	----------------

(Continued)

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	SE 1/4 SE 1/4 SE 1/4	02	T 26 S	R 28 W

2 WATER WELL OWNER: USD #102  
RR#, St. Address, Box #: PO BOX 489

Board of Agriculture, Division of Water Resources

City, State, ZIP code : CIMARRON, KS 67835-0489

Application Number: 38028

FROM	TO	LITHOLOGIC LOG
129	137	04 SANDY CLAY 20 LIMESTONE
137	161	05 SAND 01 CLAY 28 ROCK
161	172	04 SANDY CLAY 05 SAND
172	185	07 FINE SAND 01 CLAY
185	210	01 CLAY 05 SAND
210	215	07 FINE SAND
215	222	01 CLAY 28 ROCK
222	232	07 FINE SAND 01 CLAY
232	250	05 SAND 28 ROCK
250	257	01 CLAY 04 SANDY CLAY
257	291	05 SAND 28 ROCK
291	293	31 CALICHE
293	300	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/28/00 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/01/00 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

*Bruce Lichman*