

WATER WELL RECORD FORM WWC-5 KSA 82A-1212

1 LOCATION OF WATER WELL: COUNTY: 035 GRAY	FRACTION SE 1/4 SW 1/4 SE 1/4	SECTION NUMBER 04	TOWNSHIP NUMBER T 26 S	RANGE NUMBER R 28 W
---	----------------------------------	----------------------	---------------------------	------------------------

DISTANCE AND DIRECTION FROM NEAREST TOWN OR CITY STREET ADDRESS OF WELL IF LOCATED WITHIN CITY?
FROM CIMARRON; APPX 2 1/4 MILES WEST

2 WATER WELL OWNER: WARNER RANCHES, L.P.
RR#, ST. ADDRESS, Box #: PO BOX 309

BOARD OF AGRICULTURE, DIVISION OF WATER RESOURCES

CITY, STATE, ZIP CODE : CIMARRON, KS 67835-0309

APPLICATION NUMBER: 28476

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 230 ELEVATION: 0
DEPTH(S) GROUNDWATER ENCOUNTERED 1. 0 FT. 2. 0 FT. 3. 0 FT.

WELL'S STATIC WATER LEVEL 70 FT. BELOW LAND SURFACE MEASURED ON MO/DAY/YR 03/09/01
PUMP TESTDATA: WELL WATER WAS 0 FT. AFTER 0 HOURS PUMPING 0 GPM

ESTIMATED YIELD 0 GPM: WELL WATER WAS 0 FT. AFTER 0 HOURS PUMPING 0 GPM

E BORE HOLE DIAMETER 17.5 IN. TO 230 FT., AND IN. TO 0 FT.

WELL WATER TO BE USED AS: 03 FEEDLOT

WAS A CHEMICAL/BACTERIOLOGICAL SAMPLE SUBMITTED TO DEPARTMENT? NO;
IF YES, MO/DAY/YR SAMPLE WAS SUBMITTED WATER WELL DISINFECTED? YES

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

BLANK CASING DIAMETER 10 IN. TO 230 FT., DIA IN. TO 0 FT., DIA IN. TO 0 FT.

CASING HEIGHT ABOVE LAND SURFACE 12 IN., WEIGHT 11 LBS/FT. WALL THICKNESS OR GAUGE NO. .511

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: FROM 165 FT. TO 185 FT., FROM 0 FT. TO 0 FT.

FROM 205 FT. TO 225 FT., FROM 0 FT. TO 0 FT.

GRAVEL PACK INTERVALS: FROM 25 FT. TO 70 FT., FROM 0 FT. TO 0 FT.

FROM 80 FT. TO 230 FT., FROM 0 FT. TO 0 FT.

6 GROUT MATERIAL 03 BENTONITE

GROUT INTERVALS: FROM 5 FT. TO 25 FT., FROM 70 FT. TO 80 FT., FROM 0 FT. TO 0 FT.

WHAT IS THE NEAREST SOURCE OF POSSIBLE CONTAMINATION: NONE OBSERVED

DIRECTION FROM WELL?

HOW MANY FEET? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	8	31 CALICHE			
8	25	05 SAND			
25	32	05 SAND 13 FINE GRAVEL			
32	64	04 SANDY CLAY 31 CALICHE 05 SAND			
64	69	05 SAND 13 FINE GRAVEL			
69	86	01 CLAY			
86	130	05 SAND 01 CLAY			
130	149	05 SAND 13 FINE GRAVEL 28 ROCK			
149	160	01 CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: THIS WATER WELL WAS CONSTRUCTED UNDER MY JURISDICTION AND WAS COMPLETED ON (MO/DAY/YEAR) 03/09/01 AND THIS RECORD IS TRUE TO THE BEST OF MY KNOWLEDGE AND BELIEF. KANSAS WATER WELL CONTRACTOR'S LICENSE NO. 145 THIS WATER WELL RECORD WAS COMPLETED ON (MO/DAY/YR) 03/16/01 UNDER THE BUSINESS NAME OF HENKLE DRILLING & SUPPLY BY (SIGNATURE)

(CONTINUED)

WATER WELL RECORD FORM WWC-5 KSA 82A-1212

1 LOCATION OF WATER WELL: COUNTY: 035 GRAY	FRACTION SE 1/4 SW 1/4 SE 1/4	SECTION NUMBER 04	TOWNSHIP NUMBER T 26 S	RANGE NUMBER R 28 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: WARNER RANCHES, L.P.
RR#, ST. ADDRESS, Box #: PO BOX 309

BOARD OF AGRICULTURE, DIVISION OF WATER RESOURCES

CITY, STATE, ZIP CODE : CIMARRON, KS 67835-0309

APPLICATION NUMBER: 28476

FROM	TO	LITHOLOGIC LOG
160	176	05 SAND 13 FINE GRAVEL
176	185	01 CLAY
185	197	04 SANDY CLAY 07 FINE SAND
197	200	07 FINE SAND
200	210	04 SANDY CLAY 07 FINE SAND
210	225	05 SAND 28 ROCK
225	233	01 CLAY
233	236	31 CALICHE 20 LIMESTONE
236	240	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: THIS WATER WELL WAS CONSTRUCTED UNDER MY JURISDICTION AND WAS
COMPLETED ON (MO/DAY/YEAR) 03/09/01 AND THIS RECORD IS TRUE TO THE BEST OF MY KNOWLEDGE AND BELIEF. KANSAS
WATER WELL CONTRACTOR'S LICENSE NO. 145 THIS WATER WELL RECORD WAS COMPLETED ON (MO/DAY/YR) 03/16/01
UNDER THE BUSINESS NAME OF HENKLE DRILLING & SUPPLY BY (SIGNATURE) *Bonnie J. Henklein*