

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	NW 1/4 SE 1/4 NW 1/4	23	T 26 S	R 28 W

Distance and direction from nearest town or city street address of well if located within city?
FROM CIMARRON, APPX 1 1/2 MILES SOUTH

2 WATER WELL OWNER:	D M & M FARMS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	PO BOX 668	Application Number: 19116
City, State, ZIP code :	CIMARRON, KS 67835-0668	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 232 ELEVATION: 0
	Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

1 / \	WELL'S STATIC WATER LEVEL 83 ft. below land surface measured on mo/day/yr 04/21/07
	Pump test data: Well water was 158 ft. after 4 hours pumping 1823 gpm

1 ----- NW ----- NE -----	Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
M	
i W ----- ----- E Bore Hole Diameter 24 in. to 232 ft., and in. to 0 ft.	
l	

e ----- SW ----- SE -----	WELL WATER TO BE USED AS: 02 IRRIGATION
	Was a chemical/bacteriological sample submitted to department? No ;

\ /	If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL	CASING JOINTS: WELDED
---------------------------------------	-----------------------

Blank casing diameter 16 in. to 232 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 167 ft. to 227 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 232 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL
--

Direction from well? NORTHWEST How many feet? 276

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	10	04 SANDY CLAY 20 LIMESTONE			
10	42	05 SAND 11 GRAVEL			
42	57	04 SANDY CLAY			
57	60	05 SAND			
60	77	04 SANDY CLAY			
77	94	07 FINE SAND 08 MEDIUM SAND			
94	105	05 SAND 13 FINE GRAVEL			
105	109	04 SANDY CLAY			
109	128	07 FINE SAND 08 MEDIUM SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/19/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/22/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 035 GRAY	NW 1/4 SE 1/4 NW 1/4	23	T 26 S	R 28 W

2 WATER WELL OWNER: D M & M FARMS

RR#, St. Address, Box # : PO BOX 668

Board of Agriculture, Division of Water Resources

City, State, ZIP code : CIMARRON, KS 67835-0668

Application Number: 19116

FROM	TO	LITHOLOGIC LOG
128	134	05 SAND 13 FINE GRAVEL
134	138	04 SANDY CLAY
138	140	07 FINE SAND 08 MEDIUM SAND
140	146	04 SANDY CLAY
146	157	07 FINE SAND 08 MEDIUM SAND
157	168	04 SANDY CLAY
168	184	05 SAND 28 ROCK
184	227	05 SAND 28 ROCK 01 CLAY
227	240	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/19/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/22/07 under the business name of HENKLE DRILLING & SUPPLY by (signature) 