

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction COUNTY: 035 GRAY	NE 1/4 SE 1/4 SW 1/4	Section Number 27	Township Number T 26 S	Range Number R 29 W
---------------------------	------------------------------	----------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM INGALLS; APPX 4 3/4 MILES SOUTH & 1 MILE WEST

2 WATER WELL OWNER:	BAT-CO FARMS, INC.		Board of Agriculture, Division of Water Resources				
RR#, St. Address, Box # :	17704 11 ROAD		Application Number: 21367				
City, State, ZIP code :	INGALLS, KS 67853-						
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			4 DEPTH OF COMPLETED WELL	219 ELEVATION: 0			
			Depth(s) Groundwater Encountered	1. 0 ft. 2. 0 ft. 3. 0 ft.			
			WELL'S STATIC WATER LEVEL	148 ft. below land surface measured on mo/day/yr 11/23/04			
			Pump testdata: Well water was	185 ft. after 4 hours pumping 1196 gpm			
			Estimated Yield	0 gpm: Well water was	0 ft. after	0 hours pumping	0 gpm
			Bore Hole Diameter	24 in. to 219 ft., and	in. to	0 ft.	
			WELL WATER TO BE USED AS:	02 IRRIGATION			
			Was a chemical/bacteriological sample submitted to department? No ;				
			If yes, mo/day/yr sample was submitted				Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL	CASING JOINTS: WELDED
Blank casing diameter	16 in. to 219 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface	12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL	
SCREEN OR PERFORATION OPENINGS ARE:	01 CONT. SLOT
SCREEN PERFORATED INTERVALS:	From 179 ft. to 199 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 219 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE	
Grout Intervals:	From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination:	NONE OBSERVED
Direction from well?	How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	18	01 CLAY 31 CALICHE			
18	28	07 FINE SAND 01 CLAY			
28	63	01 CLAY 05 SAND			
63	116	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
116	131	01 CLAY 05 SAND			
131	143	05 SAND 01 CLAY			
143	163	04 SANDY CLAY			
163	169	05 SAND 01 CLAY			
169	180	04 SANDY CLAY 05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:	This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/18/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/13/05 under the business name of HENKLE DRILLING & SUPPLY by (signature)
--	--

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 035 GRAY	Fraction NE 1/4 SE 1/4 SE 1/4	Section Number 27	Township Number T 26 S	Range Number R 29 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: BAT-CO FARMS, INC.
RR#, St. Address, Box #: 17704 11 ROAD
City, State, ZIP code : INGALLS, KS 67853-

Board of Agriculture, Division of Water Resources
Application Number: 21367

FROM	TO	LITHOLOGIC LOG
180	199	05 SAND 11 GRAVEL 28 ROCK
199	210	01 CLAY
210	223	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/18/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/13/05 under the business name of HENKLE DRILLING & SUPPLY

by (signature) *Bennie Reichert*