

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction COUNTY: GRAY	NE 1/4 SE 1/4 NE 1/4	Section Number 10	Township Number T 26 S	Range Number R 29 W
---------------------------	--------------------------	----------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?  
FROM INGALLS - 1 1/2 MILES SOUTH ON BLACKTOP

2 WATER WELL OWNER:	GRAY CO. PUBLIC WORKS	Wells #1	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	PO BOX 688	Application Number:	
City, State, ZIP code :	CIMARRON, KS 67835		

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL 245 ELEVATION: 0 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
/ \ N W E S W S E	WELL'S STATIC WATER LEVEL 0 ft. below land surface measured on mo/day/yr / / Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm Estimated Yield 10 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 6 in. to 245 ft., and in. to 0 ft. WELL WATER TO BE USED AS: MONITORING Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC	CASING JOINTS: GLUED
Blank casing diameter 2 in. to 245 ft., Dia in. to 0 ft., Dia in. to 0 ft.	
Casing height above land surface 12 in., weight 40 lbs/ft. Wall thickness or gauge No. 40	
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC	
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT	

SCREEN PERFORATED INTERVALS:	From 120 ft. to 240 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 0 ft. to 0 ft., From 0 ft. to 0 ft.
From 115 ft. to 245 ft., From 0 ft. to 0 ft.	
From 0 ft. to 0 ft., From 0 ft. to 0 ft.	

6 GROUT MATERIAL BENTONITE	
Grout Intervals: From 0 ft. to 115 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.	
What is the nearest source of possible contamination: LANDFILL	
Direction from well?	How many feet? 0

FROM 0	TO 20	LITHOLOGIC LOG 01 TOPSOIL 02 FINE SAND	FROM	TO	PLUGGING INTERVALS
20	80	37 FIN-COAR SAN 06 SMALL GRAVEL			
80	100	02 FINE SAND			
100	120	10 FINE-MEDSAND 32 TAN CLAY			
120	160	32 TAN CLAY			
160	180	32 TAN CLAY 02 FINE SAND			
180	200	10 FINE-MEDSAND 32 TAN CLAY			
200	220	37 FIN-COAR SAN			
220	260	24 THINROCLAYER 32 TAN CLAY 07 BLUE SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/07/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/26/07 under the business name of JOE'S WELL SERVICE, INC.	by (signature) Judith Creek
--	-----------------------------