

WATER WELL RECORD Form WWC-5 KSA 82a-1212

11 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY SE 1/4 NW 1/4 NE 1/4 8 T 26 S R 29 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3 MILES WEST AND 1 3/4 MILES SOUTH OF INGALLS

12 WATER WELL OWNER: CARL D. MILLER
 RR#, St. Address, Box #: P. O. BOX 653 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : CIMARRON, KS 67835- Application Number: 15,771

13 LOCATE WELL'S LOCATION WITH 4 DEPTH OF COMPLETED WELL 265 ELEVATION: 0
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 97 ft. below land surface measured on mo/day/yr 04/06/93
 Pump testdata: Well water was 170 ft. after 4 hours pumping 1550 gpm

Estimated Yield 1550 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 265 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No
 If yes, mo/day/yr sample was submitted Water well disinfected? No

15 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED

Blank casing diameter 16 in. to 265 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 130 ft. to 150 ft., From 195 ft. to 255 ft.
 From 165 ft. to 185 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 265 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

16 GROUT MATERIAL 03 BENTONITE

Grout intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? SOUTHEAST How many feet? 150

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	7	07 FINE SAND			
7	13	01 CLAY			
13	40	07 FINE SAND 08 MEDIUM SAND			
40	43	04 SANDY CLAY 31 CALICHE			
43	50	07 FINE SAND 08 MEDIUM SAND			
50	67	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
67	72	04 SANDY CLAY			
72	86	04 SANDY CLAY 20 LIMESTONE			
86	143	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
143	164	04 SANDY CLAY 20 LIMESTONE 01 CLAY			

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/08/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction				1 Section Number	1 Township Number	1 Range Number
1 COUNTY: 035 GRAY	1 SE	1/4 NW	1/4 NE	1/4	1 8	1 T 26	S 1 R 29 W

12 WATER WELL OWNER: CARL D. MILLER

1 RR#, St. Address, Box #: P. O. BOX 653

Board of Agriculture, Division of Water Resources

1 City, State, ZIP code : CIMARRON, KS 67035-

Application Number: 15,771

FROM	TO	LITHOLOGIC LOG
164	183	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL
183	195	01 CLAY
195	216	07 FINE SAND 09 COARSE SAND 01 CLAY
216	218	01 CLAY
218	228	07 FINE SAND 13 FINE GRAVEL 12 V. FINE GRAV
228	238	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND
238	253	07 FINE SAND 09 COARSE SAND 15 CRS GRAVEL
253	255	36 GYP ROCK 20 LIMESTONE
255	262	19 SHALE

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/08/93 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

