


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

**WATER WELL RECORD**  
**KSA 82a-1201-1215**

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County Gray	Fraction NE 1/4 SW 1/4 SW 1/4	Section number 20	Township number T 26 S	Range number R 29 E/W
2. Distance and direction from nearest town or city:	4 south of Ingalls, 2 3/4 west.		3. Owner of well: R.R. or street: City, state, zip code:	Don Renick Ingalls, Ks. 67853	
4. Locate with "X" in section below:	Sketch map: 		6. Bore hole dia. 26 in. Completion date 5-31-75 Well depth 205 ft.		
5. Type and color of material	From	To	7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
			8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
			9. Casing: Material <input checked="" type="checkbox"/> Steel Height: Above <input type="checkbox"/> below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 12 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight 36.87 lbs./ft. Dia. 16 in. to 206 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gage No. 250		
			10. Screen: Manufacturer's name Johnson Type galv. Dia. 16" Slot <input type="checkbox"/> gauge Length 10 ft. Set between 160-170 ft. and 190-200 ft. Perf: 80-160 ft. and 170-190, 200-205 Gravel pack? <input type="checkbox"/> Yes Size range of material $\frac{1}{2}$ " down		
			11. Static water level: mo./day/yr. 62 ft. below land surface Date 5-22-75		
			12. Pumping level below land surfaces: 74 ft. after 2 hrs. pumping 726 g.p.m. 84 ft. after 4 hrs. pumping 1190 g.p.m. Estimated maximum yield 1190 g.p.m.		
			13. Water sample submitted: mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date		
			14. Well head completion: 12 inches above grade <input type="checkbox"/> Pitless adapter		
			15. Well grouted? <input type="checkbox"/> Yes With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.		
			16. Nearest source of possible contamination: NA ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
			17. Pump: Not installed Manufacturer's name Peerless - FMC Model number 100 HP 100 Volts Length of drop pipe 140 ft. capacity 1150 g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)			18. Elevation: Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		
19. Remarks:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter-Wilson Drilling Co. 208 Business name <input type="checkbox"/> License No. Address Box A Garden City, Ks. Signed <input type="checkbox"/> Date 9-30- Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

~~JOHN WILSON DRILLING CO.~~ **JOHN WILSON DRILLING CO.**  
INCORPORATED

Irrigation  
and Domestic  
Water Systems  
Complete Installation  
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Marvel Cattle Co.  
Gray County  
4-11-75

Location: SW<sub>1/4</sub> 20-26-29 Pivot

Test # 3

0	7	Fine sand
7	62	Brown Clay
62	112	Med. to coarse gravel (loose)
112	127	Brown clay
127	143	Fine to med. sand & gravel (loose)
143	152	Fine to med. sand & gravel, 10% clay (loose)
152	170	Fine to med. sand & gravel (loose)
170	180	Brown clay
180	200	Fine to med. sand & gravel (loose)
200	207	Brown, gray & yellow clay (hard)
207	215	Shale (hard)