

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction 1/4 SW 1/4 NE 1/4	Section number 15	Township number T 26 S R 3	Range number 11/W
2. Distance and direction from nearest town or city: Street address of well location if in city:			3. Owner of well: Reichenberger Construction R.R. or street: Box 46 City, state, zip code: Andale, Kansas		
4. Locate with "X" in section below: N W E S 1 Mile Sketch map:			6. Bore hole dia. 11 in. Completion date 2-3-76 Well depth 70 ft. 7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary 8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 70 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .200		
5. Type and color of material			From	To	10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot .06 Length 20' Set between 50 ft. and 70 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 1-1/8"
Topsoil			0	5	11. Static water level: 45 ft. below land surface Date 2-3-76 mo./day/yr.
Clay			5	38	12. Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.
Fine sand with Clay Balls			38	45	13. Water sample submitted: mo./day/yr. Yes ☐ No ☐ Date
Clay			45	50	14. Well head completion: 12 capped Pitless adapter 12 inches above grade
Medium Sand			50	55	15. Well grouted? yes With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From 6 ft. to 16 ft.
Blue Shale			55	70	16. Nearest source of possible contamination: City ft. 75 Direction East Type Sewer Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: ☒ Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 2-4- Authorized representative
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley			19. Remarks: Flat Ground Well to be in basement.		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-3