

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 035 GRAY NE 1/4 NE 1/4 SE 1/4 1/28 T 26 S R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 6 1/2 MILES SOUTH, 2 WEST & 1/2 SOUTH OF CHARLESTON

2 WATER WELL OWNER: SCHMIDT, NORMAN
 RR#, St. Address, Box #: 4502 F ROAD
 City, State, ZIP code : INGALLS, KS 67853- Board of Agriculture, Division of Water Resources
 Application Number: 17,807 & 19,294

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 349 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 170 ft. below land surface measured on mo/day/yr 07/16/95
 Pump testdata: Well water was 270 ft. after 4 hours pumping 1240 gpm

Estimated Yield 1240 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

W E Bore Hole Diameter 24 in. to 349 ft., and in. to 0 ft.

X WELL WATER TO BE USED AS: 02 IRRIGATION

SW SE Was a chemical/bacteriological sample submitted to department? No
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED

Blank casing diameter 16 in. to 349 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 206 ft. to 246 ft., From 0 ft. to 0 ft.

From 266 ft. to 346 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 20 ft. to 349 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 14 ABAND. WELL

Direction from well? NORTHEAST How many feet? 275

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	14	04 SANDY CLAY			
14	71	07 FINE SAND 08 MEDIUM SAND			
71	79	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
79	127	05 SAND 11 GRAVEL 16 V CRS GRAVEL			
127	158	04 SANDY CLAY			
158	192	05 SAND 13 FINE GRAVEL			
192	207	04 SANDY CLAY 05 SAND			
207	227	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
227	231	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/13/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/25/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

11 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
| COUNTY: 035 GRAY | NE 1/4 NE 1/4 SE 1/4 | 28 | T 26 S | R 30 W

12 WATER WELL OWNER: SCHMIDT, NORMAN
| RR#, St. Address, Box #: 4502 F ROAD
| City, State, ZIP code : INGALLS, KS 67853-
Board of Agriculture, Division of Water Resources
Application Number: 17,807 & 19,294

FROM | TO | LITHOLOGIC LOG
231 | 246 | 05 SAND 01 CLAY 13 FINE GRAVEL
246 | 264 | 04 SANDY CLAY 20 LIMESTONE
264 | 330 | 05 SAND 01 CLAY
330 | 346 | 04 SANDY CLAY 20 LIMESTONE
346 | 353 | 31 CALICHE
353 | 362 | 19 SHALE

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/13/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/25/95 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bennie J. Reichmuth