

WATER WELL RECORD Form WWC-5 KSA 82a-1212

11 LOCATION OF WATER WELL: 1 Fraction 1 Section Number 1 Township Number 1 Range Number
 COUNTY: 035 GRAY 1 NE 1/4 NW 1/4 SE 1/4 1 35 1 T 26 S 1 R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 7 3/4 SOUTH, 3/4 WEST & 1/4 SOUTH OF CHARLESTON

12 WATER WELL OWNER: SCHMIDT, HENRY

RR#, St. Address, Box #: P.O. BOX 341 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : MONTEZUMA, KS 67867- Application Number: 23,018

13 LOCATE WELL'S LOCATION WITH 1 4 DEPTH OF COMPLETED WELL 324 ELEVATION: 0
 AN "X" IN SECTION BOX: 1 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

1 NW 1 NE 1 WELL'S STATIC WATER LEVEL 133 ft. below land surface measured on mo/day/yr 02/01/96
 Pump testdata: Well water was 247 ft. after 4 hours pumping 360 gpm

1 M 1 Estimated Yield 360 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

1 W 1 E Bore Hole Diameter 24 in. to 324 ft., and in. to 0 ft.

1 e 1 WELL WATER TO BE USED AS: 02 IRRIGATION

1 SW 1 SE 1 Was a chemical/bacteriological sample submitted to department? No ;
 1 / 1 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

15 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED

1 Blank casing diameter 16 in. to 324 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250

1 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL

1 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

1 SCREEN PERFORATED INTERVALS: From 165 ft. to 285 ft., From 0 ft. to 0 ft.
 From 307 ft. to 317 ft., From 0 ft. to 0 ft.

1 GRAVEL PACK INTERVALS: From 20 ft. to 324 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

16 GROUT MATERIAL 03 BENTONITE

1 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

1 What is the nearest source of possible contamination: 14 ABAND. WELL

1 Direction from well? SOUTHEAST How many feet? 1075

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	10	01 CLAY			
10	25	04 SANDY CLAY 07 FINE SAND			
25	40	07 FINE SAND 08 MEDIUM SAND 31 CALICHE			
40	75	07 FINE SAND 08 MEDIUM SAND 31 CALICHE			
75	95	09 COARSE SAND 11 GRAVEL 01 CLAY			
95	120	04 SANDY CLAY 31 CALICHE 05 SAND			
120	150	17 SAND & GRAVL 01 CLAY 31 CALICHE			
150	160	01 CLAY 05 SAND			
160	170	05 SAND 01 CLAY			

17 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/30/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/08/96 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: I Fraction I Section Number I Township Number I Range Number
1 COUNTY: 035 GRAY I NC 1/4 NW 1/4 SE 1/4 I 35 I T 26 S I R 30 W

2 WATER WELL OWNER: SCHMIDT, HENRY
1 RR#, St. Address, Box # : P.O. BOX 341
1 City, State, ZIP code : MONTEZUMA, KS 67867- Board of Agriculture, Division of Water Resources
Application Number: 23,018

FROM	TO	LITHOLOGIC LOG
170	213	05 SAND 01 CLAY
213	225	01 CLAY 04 SANDY CLAY 05 SAND
225	241	05 SAND 04 SANDY CLAY
241	285	05 SAND 04 SANDY CLAY
285	305	01 CLAY 31 CALICHE 05 SAND
305	309	19 SHALE 23 SANDSTONE
309	314	07 FINE SAND 19 SHALE
314	320	19 SHALE 23 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/30/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/08/96 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Henry Schmidt