

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number
 COUNTY: 035 GRAY : NW 1/4 NW 1/4 NW 1/4 : 27 : T 26 S : R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 3/4 MILES WEST AND 6 3/4 MILES SOUTH OF CHARLESTON.

2 WATER WELL OWNER: SCHMIDT, LLOYD
 RR#, St. Address, Box #: BOX 102, RT. 1 Board of Agriculture, Division of Water Resources

3 City, State, ZIP code : INGALLS, KS 67853- Application Number:

4 LOCATE WELL'S LOCATION WITH : 4 DEPTH OF COMPLETED WELL 340 ELEVATION:
 AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 160 ft. 2. ft. 3. ft.

X					WELL'S STATIC WATER LEVEL 160 ft. below land surface measured on mo/day/yr 06/17/91
1	--- NW ---	NE ---			Pump testdata: Well water was ft. after hours pumping gpm
M					Estimated Yield gpm: Well water was ft. after hours pumping gpm
i	W		E		Bore Hole Diameter 10 in. to 340 ft., and in. to ft.
l					WELL WATER TO BE USED AS: 01 DOMESTIC
e	--- SW ---	SE ---			Was a chemical/bacteriological sample submitted to department? No ;
\					If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 340 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 220 ft. to 240 ft., From ft. to ft.
 From 300 ft. to 340 ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 340 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From ft. to 14 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: 10 LIVEST. PENS
 Direction from well? EAST How many feet? 100

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	3	04 SANDY CLAY			
3	46	01 CLAY			
46	56	07 FINE SAND			
56	74	04 SANDY CLAY 07 FINE SAND			
74	84	04 SANDY CLAY 20 LIMESTONE			
84	126	08 MEDIUM SAND 14 MED GRAVEL 23 SANDSTONE			
126	143	04 SANDY CLAY			
143	166	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
166	212	04 SANDY CLAY 05 SAND			
212	238	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/18/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/01/91 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas M. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number
COUNTY: 035 GRAY NW 1/4 NW 1/4 NW 1/4 27 T 26 S R 30 W

2 WATER WELL OWNER: SCHMIDT, LLOYD
RR#, St. Address, Box #: BOX 102, RT. 1
Board of Agriculture, Division of Water Resources

3 City, State, ZIP code : INGALLS, KS 67853- Application Number:

FROM	TO	LITHOLOGIC LOG
238	265	04 SANDY CLAY 20 LIMESTONE
265	272	06 VERY FN SAND 07 FINE SAND
272	280	04 SANDY CLAY 05 SAND
280	302	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL
302	310	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY
310	340	08 MEDIUM SAND 13 FINE GRAVEL 01 CLAY
340	351	01 CLAY 19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/18/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/01/91 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

