


USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Gray	Fraction NE 1/4 SW 1/4 NE 1/4	Section number 36-	Township number T 26 S	Range number R 30
2. Distance and direction from nearest town or city: 8 south, 1 east 1/4 south, 1/4 west of Charleston Street address of well location if in city:				3. Owner of well: Lloyd Schmidt R.R. or street: Montezuma, KS 67867 City, state, zip code:		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 26 in. Completion date 9-21-76 Well depth 249 ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
5. Type and color of material		From	To	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 36.87 lbs./ft. Dia. 16 in. to 250 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. ☐		
				10. Screen: Manufacturer's name Johnson Type ☐ Dia. 16" Slot/gauze ☐ Length 20' Set between 190 ft. and 210 ft. Perf: 90-190 ft. and 210-249 ft. Gravel pack? yes Size range of material 1/4" Down		
				11. Static water level: ☐ mo./day/yr. 66 ft. below land surface Date 9-16-76		
				12. Pumping level below land surfaces: 1500 94 ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1500 g.p.m.		
				13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐		
				14. Well head completion: 12 inches above grade ☐ Pitless adapter		
				15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
				16. Nearest source of possible contamination: N/A ft. ☐ Direction ☐ Type Field MAC Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☐ Not installed Manufacturer's name Goulds U.S. Pumps Model number 12 JHC HP 125 Volts ☐ Length of drop pipe 160 ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:	19. Remarks:			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter Wilson Drilling 208 Business name License No. 208 Address Box A Garden City, KS 67845 Signed [Signature] Date 9-24-76 Authorized representative		
Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

The Professionals

MINTER-WILSON DRILLING CO.
INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

LEO SCHMIDT
GRAY COUNTY
3-25-76

LOCATION: HWY 36-26-30
1/2 Mile North From South Pivot

STATIC WATER LEVEL: 65'

TEST # PIVOT 2

1	2	Top Soil
2	19	Fine Sand
19	23	Brown Sandy Clay
23	35	Fine Sand, Clay Streak
35	50	Fine To Med. Sand, Some Coarse Gravel (Loose)
50	97	Coarse Gravel (Loose)
97	110	Fine To Med. Sand, Gravel
110	117	Brown Sand, Clay
117	127	Fine To Med. Sand, Gravel
127	135	Brown Sandy Clay
135	140	Brown Sandy Clay, Sand Streak
140	143	Fine To Med. Sand (Loose)
143	168	Fine To Med. Sand, Gravel (Loose)
168	177	Brown Clay, Stick
177	210	Fine To Med. Sand, Gravel
210	213	Brown Sandy Clay
213	230	Fine To Med. Sand, Gravel (Loose)
230	234	Brown Sandy Clay (Hard)
234	249	Fine To Med. Sand, Gravel, Mixed with Brown Rock
249	257	Brown Sandy Clay
257	262	Yellow Clay
262	267	Shale