

## **WATER WELL RECORD**

**Form WWC-5**

Division of Water Resources App. No.

21,384 D7

**7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:** This water well was  constructed,  reconstructed, or  plugged under my jurisdiction and was completed on (mo/day/year) 5-31-12 ..... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 208 ..... This Water Well Record was completed on (mo/day/year) 6-5-12 ..... under the business name of MINTER-WILSON DRILLING CO., INC. ..... by (signature) Nora Keller .....

**INSTRUCTIONS:** Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. I include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>.

*The  
Professionals*

# MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation  
and Domestic  
Water Systems  
Complete Installation  
and Repairing

Phone 620-276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

NAME            DAVE REYNOLDS - ROCKING R  
COUNTY        GRAY  
DATE            4-27-12

LOCATION:    SE 1/4 5-26-30 - PIERCEVILLE-PLYMELL INTERSECTION -  
                  3-1/2 MILES EAST & 1/2 MILE NORTH  
                  - NORTHWEST EDGE OF CIRCLE # 66

STATIC WATER LEVEL - APPROX. 195 FT.

## TEST # 2

0' TO 60' - SAND WITH STRIPS OF BROWN SANDY CLAY  
60' TO 180' - FINE TO MEDIUM SAND & GRAVEL - SOME COARSE  
180' TO 195' - BROWN SANDY CLAY  
                  WITH STRIPS OF WHITE ROCK  
195' TO 207' - FINE TO MEDIUM SAND & GRAVEL  
207' TO 220' - BROWN SANDY CLAY  
                  WITH LAYERS OF SAND & GRAVEL  
220' TO 235' - FINE TO MEDIUM SAND  
                  WITH STRIPS OF BROWN SANDY CLAY  
235' TO 240' - BROWN SANDY CLAY  
240' TO 265' - FINE TO MEDIUM SAND - SOME SMALL GRAVEL  
                  WITH 20% BROWN SANDY CLAY  
265' TO 275' - FINE TO MEDIUM SAND & GRAVEL  
275' TO 280' - BROWN SANDY CLAY  
280' TO 285' - FINE TO MEDIUM SAND & GRAVEL  
285' TO 300' - BROWN SANDY CLAY  
300' TO 308' - FINE TO MEDIUM SAND  
                  WITH STRIPS OF HARD WHITE ROCK - 40%  
308' TO 312' - BROWN & YELLOW CLAY - 250 PULL DOWN  
312' TO 320' - SHALE - 250 PULL DOWN