

6894

KSA 82a-1212

**Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing**

Phone 276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

LOCATION: NW 1/3 6-26-31 - HWY. 83 & PARALLEL ROAD - 6 MILES EAST
3/8THS OF A MILE SOUTH
- 300 FT. NORTH OF EXISTING WELL

STATIC WATER LEVEL - 160 FT.

0' TO 1' - TOP SOIL
1' TO 9' - BROWN SANDY CLAY
9' TO 34' - BROWN CLAY
34' TO 52' - FINE TO MEDIUM SAND & GRAVEL
52' TO 128' - FINE TO MEDIUM SAND & GRAVEL - SOME COARSE
128' TO 146' - BROWN SANDY CLAY
146' TO 171' - FINE TO MEDIUM SAND & GRAVEL
171' TO 188' - BROWN SANDY CLAY - TIGHT
188' TO 202' - BROWN CLAY
202' TO 221' - FINE TO MEDIUM SAND & FINE GRAVEL WITH CLAY STRIPS
221' TO 246' - BROWN CLAY
246' TO 263' - BROWN CLAY WITH GRAVEL STREAK - TIGHT
263' TO 274' - FINE TO MEDIUM SAND & FINE GRAVEL - 10% CLAY
274' TO 287' - BROWN SANDY CLAY
287' TO 313' - FINE TO MEDIUM SAND & GRAVEL - BROWN ROCK & 15% CLAY
313' TO 324' - BROWN CLAY
324' TO 334' - FINE TO MEDIUM SAND - 15% CLAY
334' TO 361' - BROWN SANDY CLAY - TIGHT
361' TO 367' - BROWN YELLOW CLAY - HARD PULL DOWN
367' TO 380' - SHALE - HARD PULL DOWN