


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County <u>Finney</u>	Fraction <u>Center</u> 1/4 1/4 1/4	Section number <u>NW 29</u>	Township number <u>T 26</u> S <u>R 33</u>	Range number <u>33</u> (W)
2. Distance and direction from nearest town or city: <u>12 South - 5 West of Garden City</u> Street address of well location if in city:			3. Owner of well: <u>Dean & Jerry Gigot - Greenslate</u> R.R. or street: <u>Star Route</u> City, state, zip code: <u>Garden City, Kansas 67846</u>		
4. Locate with "X" in section below: <div style="text-align: center;">N 1 Mile W  E S 1 Mile</div>			Sketch map:		
5. Type and color of material			From	To	
			<u>Surface clay sand and gravel</u> <u>0</u> <u>100</u>		
			<u>Medium to coarse sand and gravel</u> <u>100</u> <u>140</u>		
			<u>Brown clay with medium to coarse sand</u> <u>140</u> <u>200</u>		
			<u>Fine medium and loose with sand streaks</u> <u>200</u> <u>300</u>		
<u>Sandy clay with medium to coarse sand</u> <u>300</u> <u>362</u>			6. Bore hole dia. <u>26</u> in. Completion date <u>3-29-75</u> Well depth <u>362</u> ft.		
			7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
			8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
			9. Casing: Material <u>steel</u> Height <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>18</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>54</u> lbs./ft. Dia. <u>18</u> in. to <u>362</u> ft. depth Wall Thickness: inches or Dia. <u>18</u> in. to <u>362</u> ft. depth gage No. <u>288</u>		
			10. Screen: Manufacturer's name <u>Gensco Inc.</u> Type <u>Mfg. slotted</u> Dia. <u>18"</u> <u>1 1/8 x 32 row</u> Length <u>362</u> ft. Set between <u>104</u> ft. and <u>362</u> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>1/8</u> ft.		
			11. Static water level: <u>124</u> ft. below land surface Date <u>7-24-75</u> mg./day/yr.		
			12. Pumping level below land surfaces: <u>125</u> ft. after <u>5</u> hrs. pumping <u>1500</u> g.p.m. <u>125</u> ft. after <u>20</u> hrs. pumping <u>1500</u> g.p.m. Estimated maximum yield <u>1650</u> g.p.m.		
			13. Water sample submitted: <u>mo./day/yr.</u> <input type="checkbox"/> Yes <input type="checkbox"/> No Date <u>7-24-75</u>		
			14. Well head completion: <input type="checkbox"/> Pitless adapter <u>18</u> inches above grade		
			15. Well grouted? <u>see remarks</u> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u> </u> ft. to <u> </u> ft.		
			16. Nearest source of possible contamination: ft. <u> </u> Direction <u>NONE CLOSE</u> Type <u> </u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
			17. Pump: <u>Not installed</u> Manufacturer's name <u>Peerless Pump</u> Model number <u>LB-12</u> HP <u>105</u> Volts <u>480</u> Length of drop pipe <u>180</u> ft. capacity <u>800</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)					
18. Elevation:	19. Remarks: <u>Grout furnished by customer</u>		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>C. B. Adams Drilling Co.</u> <u>292</u> Business name License No. Address <u>W. Hwy 50 Garden City</u> Signed <u>C. B. Adams</u> Date <u>5-17-76</u> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5