

LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: PINNEY SW 1/4 SW 1/4 NE 1/4 X 5 T 26 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM PLYMILL ON PLYMILL ROAD 1/2 NORTH & 1/2 WEST

WATER WELL OWNER: STONE, BILL
 RR#, St. Address, Box #: 12645 S STONE ROAD Board of Agriculture, Division of Water Resources
 City, State, ZIP code: GARDEN CITY, KS 67846- Application Number:

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 505 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 202 ft. below land surface measured on mo/day/yr 01/31/05

Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 60 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 505 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 505 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 320 ft. to 360 ft., From 0 ft. to 0 ft.
 From 460 ft. to 500 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 27 ft. to 505 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GROUT MATERIAL BENTONITE

Grout intervals: From 6 ft. to 27 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: NONE

Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 05 CLAY			
20	40	05 CLAY			
40	60	05 CLAY 10 FINE-MEDSAND			
60	105	37 FIN-COAR SAN 06 SMALL GRAVEL 23 MEDIUM			
105	170	32 TAN CLAY			
170	240	36 BLUE CLAY 24 THINROCLAYER			
240	260	36 BLUE CLAY 02 FINE SAND			
260	350	37 FIN-COAR SAN 06 SMALL GRAVEL			
350	370	17 CLAY LAYERS 37 FIN-COAR SAN			
370	400	37 FIN-COAR SAN 17 CLAY LAYERS			

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/01/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 02/07/05 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Janet C. Calk*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: FINNEY	SW 1/4 SW 1/4 NE 1/4	6	T 26 S	R 33 W

WATER WELL OWNER: STONE, BILL

RE#, St. Address, Box #: 12645 S STONE ROAD

Board of Agriculture, Division of Water Resources

City, State, ZIP code: GARDEN CITY, KS 67846-

Application Number:

FROM	TO	LITHOLOGIC LOG
400	420	10 FINE-MEDSAND
420	460	10 FINE-MEDSAND 17 CLAY LAYERS
460	480	10 FINE-MEDSAND 05 CLAY
480	500	05 CLAY 37 FIN-COAR SAN 27 ROCK (Brown)
500	520	27 ROCK 05 CLAY (Brown)

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/01/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 02/07/05 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Joel C. Calk*