

CORRECTION(S) TO WATER WELL RECORD (WWC-5)

(to rectify lacking or incorrect information)

County: Finney

Location listed as:

Section-Township-Range: 36-245-34W

Fraction ($\frac{1}{4}$ $\frac{1}{4}$ $\frac{1}{4}$): C NW

Location changed to:

23-265-34W

S2 S2 N2 NW

Other changes: Initial statements: _____

Changed to: _____

Comments: _____

verification method: Written description, water rights information in
WIMAS database, county ownership map, and mapping tool
& aerial photos on KGS website. initials: DRL date: 6/30/2010

submitted by: Kansas Geological Survey, Data Resources Library, 1930 Constant Ave., Lawrence, KS 66047-3726

to: Kansas Dept of Health & Environment, Bureau of Water, 1000 SW Jackson, Suite 420, Topeka, KS 66612-1367.

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 028 FINNEY NEAR 1/4 CENTR 1/4 NW 1/4 36 T 24 S R 34 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 12 MILES S, 7 1/2 W, 1/4 S, 1/4 W, OF GARDEN CITY

2 WATER WELL OWNER: CIRCLE LAND & CATTLE
 RR#, St. Address, Box #: P. O. BOX 739 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: GARDEN CITY, KS 67846- Application Number: 22,577

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 468 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 167 ft. below land surface measured on mo/day/yr 05/04/96
 Pump test data: Well water was 258 ft. after 4 hours pumping 1205 gpm

Estimated Yield 1205 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 468 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 468 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 215 ft. to 335 ft., From 453 ft. to 463 ft.
 From 393 ft. to 433 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 468 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? SOUTH How many feet? 150

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	8	07 FINE SAND			
8	14	04 SANDY CLAY			
14	30	07 FINE SAND 08 MEDIUM SAND			
30	63	05 SAND 11 GRAVEL			
63	90	05 SAND 11 GRAVEL 04 SANDY CLAY			
90	105	04 SANDY CLAY 31 CALICHE			
105	114	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND			
114	168	05 SAND 04 SANDY CLAY			
168	223	05 SAND 04 SANDY CLAY			
223	257	05 SAND 04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was
 completed on (mo/day/year) 05/02/96 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/14/96
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 028 FINNEY | NEAR 1/4 CENTR 1/4 NW 1/4 | 36 | T 24 S | R 34 W

2 WATER WELL OWNER: CIRCLE LAND & CATTLE
RR#, St. Address, Box #: P. O. BOX 739
City, State, ZIP code: GARDEN CITY, KS 67846-
Board of Agriculture, Division of Water Resources
Application Number: 22,577

FROM	TO	LITHOLOGIC LOG
257	286	04 SANDY CLAY 05 SAND
286	305	04 SANDY CLAY 05 SAND
305	325	04 SANDY CLAY 05 SAND
325	335	05 SAND 04 SANDY CLAY 31 CALICHE
335	390	01 CLAY 04 SANDY CLAY 20 LIMESTONE
390	405	05 SAND 04 SANDY CLAY
405	436	28 ROCK 23 SANDSTONE 31 CALICHE
436	451	19 SHALE
451	465	23 SANDSTONE 19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/02/96 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/14/96
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Leichman*